


STANDARDS DEVELOPMENT BRANCH OMCE



36936000004643

HYDROGEOLOGICAL ASSESSMENT OF THE CLOSED COBOCONK LANDFILL

OCTOBER 1989



Environment
Ontario

Jim Bradley
Minister

Copyright Provisions and Restrictions on Copying:

This Ontario Ministry of the Environment work is protected by Crown copyright (unless otherwise indicated), which is held by the Queen's Printer for Ontario. It may be reproduced for non-commercial purposes if credit is given and Crown copyright is acknowledged.

It may not be reproduced, in all or in part, for any commercial purpose except under a licence from the Queen's Printer for Ontario.

For information on reproducing Government of Ontario works, please contact ServiceOntario Publications at copyright@ontario.ca

HYDROGEOLOGICAL ASSESSMENT
OF THE
CLOSED COBOCONK LANDFILL

Report Prepared for:
Waste Management Branch

Report prepared by:
Gartner Lee Limited

OCTOBER 1989



Copyright: Queen's Printer for Ontario, 1989
This publication may be reproduced for non-commercial purposes
with appropriate attribution.

DISCLAIMER

This report was prepared for the Ontario Ministry of the Environment as part of a ministry-funded project. The views and ideas expressed in this report are those of the author and do not necessarily reflect the views and policies of the Ministry of the Environment, nor does mention of trade names or commercial products constitute endorsement or recommendation for use.




TABLE OF CONTENTS

	<u>PAGE</u>
EXECUTIVE SUMMARY	i
1.0 INTRODUCTION	1
2.0 BACKGROUND AND LANDFILL HISTORY	3
3.0 PHYSICAL SETTING	6
4.0 GEOLOGY	13
5.0 WATER BUDGET	15
6.0 GROUND WATER USE	17
7.0 GROUND WATER FLOW	19
8.0 WATER QUALITY IN GROUND WATER MONITORS	25
9.0 WATER QUALITY IN RESIDENTIAL WELLS	29
11.0 SURFACE WATER QUALITY	33
12.0 LANDFILL GAS	35
13.0 CONCLUSIONS	37
14.0 RECOMMENDATIONS	39
15.0 SELECTED REFERENCES	40

LIST OF FIGURES

FIGURE 1 SITE LOCATION PLAN	4
FIGURE 2 1969 AERIAL PHOTOGRAPH	7
FIGURE 3 1978 AERIAL PHOTOGRAPH	8
FIGURE 4 1987 AERIAL PHOTOGRAPH	9
FIGURE 5 CROSS-SECTIONS A-A' AND B-B'	11
FIGURE 6 SITE PLAN	12
FIGURE 7 MEAN MONTHLY PRECIPITATION	16
FIGURE 8 ACTUAL WATER BALANCE	16
FIGURE 9 WATER TABLE ELEVATIONS, AUGUST 25, 1988	20
FIGURE 10 WATER TABLE ELEVATIONS, NOVEMBER 11, 1988	21




LIST OF TABLES

	<u>PAGE</u>
TABLE 1 WATER BALANCE CALCULATION	16
TABLE 2 SUMMARY OF HYDRAULIC CONDUCTIVITIES OF THE LIMESTONE BEDROCK BASED ON SLUG TEST RESULTS	24
TABLE 3 SUMMARY OF WATER QUALITY IN GROUND WATER MONITORS	26
TABLE 4 DRINKING WATER OBJECTIVES EXCEEDANCES	28
TABLE 5 SUMMARY OF WATER QUALITY IN RESIDENTIAL WELLS	30
TABLE 6 SUMMARY OF SURFACE WATER QUALITY	34

APPENDICES

APPENDIX I	-	MOE FILE INFORMATION
APPENDIX II	-	MOE COMPUTERIZED WATER WELL RECORDS
	-	MOE ORIGINAL WATER WELL RECORDS
	-	GLL WATER WELL RECONNAISSANCE SURVEY FORMS
APPENDIX III	-	BOREHOLE LOGS
	-	HAND AUGER BOREHOLE LOGS
	-	MONITOR DETAILS SUMMARY
	-	SLUG TEST ANALYSIS PLOTS
APPENDIX IV	-	ROUTINE WATER CHEMISTRY ANALYSES - AUGUST 1988 SAMPLES
		ROUTINE WATER CHEMISTRY ANALYSES - NOVEMBER 1988 SAMPLES
		VOLATILE ORGANIC ANALYSES OF LEACHATE (MONITOR 4-I)
		PHENOL ANALYSES OF LEACHATE (MONITORS 2-II, 3-II, 4-I)
		HEAVY METAL ANALYSES OF LEACHATE (MONITOR 4-I)




EXECUTIVE SUMMARY

The closed Coboconk Landfill is a small (0.5 hectare) landfill which was owned by the Township of Sommerville and was closed in 1974. The landfill was operated for most of its life as an open-face dump. Refuse was dumped off a bedrock scarp onto a lower area and burning of refuse was carried out on a regular basis.


The site is located on a flat lying, poorly drained, limestone plain. The refuse was placed directly on top of fractured limestone bedrock which forms the most important water supply aquifer for residents in the area. The nearest surface water courses to the landfill are the Gull River, 500 m to the west and a drainage ditch in the bottom of the Cedarhurst Quarry, 400 m to the north.

The results of this hydrogeological investigation indicate that landfill leachate presently has negligible impact on ground water quality in the limestone aquifer. The leachate tested in the study has exceptionally low concentrations compared to other Ontario landfills. This is probably due to the small size of the landfill, the age of the waste, and the fact that most of the refuse was burned. Dilution of leachate with clean ground water flowing beneath the landfill is also occurring. There are no detectable impacts on local residential wells related to leachate effects. The reasons for this are probably the dilute nature of the leachate, and additional dilution and attenuation along the ground water flow path. Based on our understanding of the landfill history and ground water flow system there is no reason to expect that leachate impacts will become worse in the future.

No leachate impacts on surface water quality were detected in this study. No methane gas concentrations were detected in the landfill and off-site methane gas migration appears highly unlikely based on our understanding of the hydrogeological setting.



Based on the findings of this hydrogeological assessment we have recommended that no remedial measures are required to contain or control leachate or methane gas at this site. Furthermore, there is no apparent need for monitoring of ground water, surface water or methane gas.



1.0 INTRODUCTION

Gartner Lee Limited (GLL) was retained by the Ontario Ministry of the Environment (MOE) (P.O. #A-05690) in August 1988 to carry out a hydrogeological assessment of the closed Coboconk Landfill.

As outlined in the MOE Request for Proposals, this hydrogeological assessment represents part of Phase III of a MOE program designed to investigate and monitor all active and closed waste disposal sites in the Province. The aim of this program is to ensure that all pertinent information regarding waste disposal sites is available for the definition of both existing impacts and the potential for future impacts on humans or the environment. Once existing or potential impacts have been identified, remedial options can be investigated and implemented where necessary.

The program has been subdivided into four separate phases:

- PHASE I: the creation and continual updating and verification of an inventory listing all active and closed waste disposal sites in the Province;
- PHASE II: preliminary file and field investigations to classify and establish a priority for further investigation;
- PHASE III: investigations and monitoring to assess site hydrogeology as well as surface and ground water contamination potential at selected sites;
- PHASE IV: investigations of remedial options at sites identified during Phase III.

The impact assessments and identification of the contamination problems related to landfills involves both surface and ground water investigations. An accurate definition




of site hydrogeology is necessary due to the Ministry's concern for the potential for hidden problems which may be affecting ground water resources.

The Phase III study described herein forms the basis for determining whether or not detailed investigations of remedial options are required at this site during Phase IV of the program.

The purpose of this Phase III study on the closed Coboconk Landfill is to define any impacts of risks the site may pose to human health and safety or the environment and to recommend any remedial measures or additional work necessary to remove or minimize such impacts or risks.

The four main objectives of this Phase III investigation are as follows:

- a) to assess any existing or potential future landfill leachate impacts on ground water and the local aquifers;
- b) to assess any existing or potential future landfill leachate impacts on surface water;
- c) to assess any existing or potential future landfill gas impacts;
- d) to determine the need for site improvements such as remedial measures or monitoring.



2.0 BACKGROUND AND LANDFILL HISTORY

The closed Coboconk Landfill is located on parts of Lots 35 and 36 of Concession Fronting on River, Township of Somerville, Victoria County, Ontario. The site is about 0.4 km southeast of the Village of Coboconk as shown on Figure 1. The area of refuse disposal is about 0.5 hectares.

Information on the history of this site was obtained from a review of MOE files. Photocopies of pertinent documents are included in Appendix I for reference.

The landfill site was owned and operated by the Township of Somerville. The date when landfilling commenced is not known but review of historical aerial photographs indicate that the site was well established in 1969. The site received a Provisional Certificate of Approval for a Waste Disposal Site (No. 321603) in November 1971. The site was closed in August 1974 due to an unsuitable hydrogeological setting and a lack of available cover material on-site.

The property on which the landfill is located was sold to a Mr. G. Mitchell in 1986 and was resold to Mr. R. Boyce in 1987. We understand that both Mr. Mitchell and Mr. Boyce were aware of the waste disposal site prior to purchasing the property.

The landfill received wastes from Somerville Township, the Village of Coboconk, and Bexley Township. It serviced a population of about 1,000 to 1,300 people and is reported to have received about 2.5 tons/day of wastes.

The composition of the wastes are estimated to be as follows:

- 60% domestic
- 25% commercial
- 5% industrial
- 4% agricultural
- 6% other





Figure 1
SITE LOCATION MAP

SCALE 1:50,000


GLL PROJECT 88-237





On some of the earlier documents the 5% industrial listed above is broken into 3% industrial and 2% hazardous wastes. However, a January 1987 letter from the Peterborough District MOE office revised this classification as shown above based on information received from the Township Reeve.

The landfill was operated as an open face dump for most of its life. Refuse was dumped off the north face of a 3 m high bedrock scarp into a lower area and filling probably proceeded in a northerly manner. Refuse was burned on a regular basis. Covering of refuse was reportedly carried out every two weeks, however lack cover material on-site probably made this task very difficult. Refuse is still visible along the north face.



3.0 PHYSICAL SETTING

The closed Coboconk Landfill is located in a rural, uplands area about 0.4 km southeast of the Village of Coboconk.

The area is described as a limestone plain by Chapman and Putnam, (1972). The main topographic relief in the area is the Gull River Valley which has cut about 20 m into the limestone plain. The Gull River is located about 0.5 km west of the landfill at its' closest point and flows in a southerly direction from Shadow Lake to Balsam Lake.

The Cedarhurst Limestone Quarry, which is located 0.3 km north of the landfill, also provides about 15 m of topographic relief. There is a drainage ditch in the bottom of the quarry which flows westward towards the river.

No flowing streams were observed during site visits on the landfill property. The area is poorly drained and bogs and swamps are present nearby.

Historical aerial photographs of the site from 1969, 1978 and 1987 were stereoscopically interpreted to provide a terrain analysis of the area. These aerial photographs are presented in Figures 2, 3 and 4.

Figure 2 illustrates that the landfill was well established in 1969. Quarries are apparent to the north and west of the site and bogs or swamps are present to the south and east. A bedrock scarp is also apparent just west of the landfill. No vegetation is established on the landfill.

Figure 3 shows the site in 1978, four years after it closed. Some vegetation is established on the landfill but most of the area appears largely unchanged from 1969. Both quarries are unchanged which suggests they were largely inactive during this period.

Figure 4 shows the site in 1987, thirteen years after closure. The landfill is covered with shrubs, trees and grasses. The access road into the site is partially overgrown. A new




Figure 2
Closed Coboconk Waste Disposal Site
1969 Aerial Photograph

Scale 1:5,000 approx.

Project 88-237



Gartner
Lee




Figure 3

Closed Coboconk Waste Disposal Site

1978 Aerial Photograph

Scale 1:5,000 approx.

Project 88-237



Gartner
Lee





Figure 4
Closed Coboconk Waste Disposal Site
 1987 Aerial Photograph

Scale 1:5,000 approx

Project 88-237




Gartner
 Lee




house has been built on 7th Line Road about 180 m northwest of the landfill.

Cedarhurst Quarry to the north has expanded and a large area of land has been cleared presumably for additional quarrying in the future. The quarry to the west remains unchanged from conditions in 1969.

Figure 5 presents two cross-sections which illustrate how the landfill is related to the major topographic features in the area. Section A-A' runs east-west and Section B-B' runs north-south as shown on the site plan, Figure 6. Section A-A' shows how the land surface and the inferred water table slope eastward to the Gull River. Section B-B' illustrates how the grades in the Cedarhurst Limestone Quarry relate to the landfill and locally affect the water table elevation. The bedrock scarp at the south end of the landfill is also apparent on Section B-B'.





Legend

- PROPERTY BOUNDARY
- ESTIMATED EXTENT OF REFUSE
- BH3 GLL BOREHOLE AND GROUND WATER MONITOR LOCATION
- H7(5011) DOMESTIC WELL SAMPLING LOCATION WITH MOE WELL RECORD NO. IN BRACKETS
- R1 SURFACE WATER SAMPLING LOCATION
- AH5 HAND AUGER BOREHOLE AND COMBUSTIBLE GAS TESTING LOCATION
- CROSS-SECTION LINE

AERIAL PHOTOGRAPHY - 1978

SCALE 1:2000 approx.

SITE PLAN

Figure
6

CLOSED COBOCONK LANDFILL
HYDROGEOLOGICAL ASSESSMENT
for the
Ministry of the Environment

GLL PROJECT 88-237



Gartner
Lee



4.0 GEOLOGY


According to geological mapping (Liberty, 1969) the bedrock at this site consists of the Middle Ordovician Black River Group. Near surface the Bobcaygeon Formation lower member occurs. This is a grey fine grained argillaceous limestone. Below this occurs the lithographic limestones of the Gull River Formation. The contact between these two horizontally bedded limestone formations reportedly occurs at surface just west of the site.

Excellent vertical exposures of the bedrock are provided in the quarry north of the site and in the Highway 35 roadcut northwest of the site. Horizontal and vertical fractures are present in the rock as well as the horizontal bedding planes. Numerous flat lying limestone outcrops are visible at the landfill site, particularly on the south and west sides.


Quaternary geological mapping by Finamore and Bajc (1983) indicates that the area of the landfill is mapped as bedrock-drift complex. This is a discontinuous veneer of glacial drift which in places is sufficiently thick to subdue bedrock topography. This drift is very thin at the landfill site.

Seven boreholes were drilled at the site between August 15th and 19th, 1988, using a track mounted CME 55 drill rig. Boreholes were advanced using casing, NQ coring bit and/or tri-cone depending on the nature of the borehole. At three locations (BH1, BH2, BH3) two boreholes were drilled in order to permit installation of both deep ($\pm 10\text{m}$) ground water monitors (1-I, 2-I, 3-I) and shallow ($\pm 5\text{m}$) ground water monitors (1-II, 2-II, 3-II). The deep boreholes were cored and the shallow monitors were tri-coned. Water was trucked from the Gull River for drilling purposes. Only one borehole was drilled and one ground water monitor was installed at location BH4. The cored samples were geologically logged by GLL's supervising geologist. Geologic borehole logs are presented in Appendix III. Borehole locations are shown on Figure 6.

Limestone bedrock was encountered at surface in boreholes 1 and 2. Borehole 3 encountered 0.3 m of sandy silt topsoil above the limestone bedrock. Borehole 4



Limestone bedrock was encountered at surface in boreholes 1 and 2. Borehole 3 encountered 0.3 m of sandy silt topsoil above the limestone bedrock. Borehole 4 encountered 3.5 m of refuse and fill above the bedrock. All boreholes were terminated in limestone bedrock.



5.0 WATER BUDGET

Long term meteorological data for Coboconk meteorological station have been reviewed to prepare a water budget for this site.

The mean annual precipitation at Coboconk is 909 mm per year, based on 11 years of meteorological data from 1970 to 1980. There is some variation, from year to year, in the total annual precipitation (standard deviation of 108 mm about the mean value). The distribution of the precipitation varies from month to month, as shown on Figure 7, for a normal year.

A water balance has been prepared using the method described in Thornthwaite and Mather (1957), as shown on Table 1. The mean annual evapotranspiration is estimated to be 537 mm, based on an assumed soil moisture storage of 100 mm. The mean annual water surplus is calculated to be 372 mm.

The distribution of the surplus water on a monthly basis through a normal year is shown on Figure 8. It shows that a significant surplus of 440 mm occurs during the autumn, winter and spring months and a deficit of 68 mm occurs during the summer.

The water surplus comprises both the surface runoff and infiltration components of the water balance. Due to the relatively flat topography and presence of fractured limestone near surface at this site it seems likely that most of the water surplus infiltrates.

TABLE 1

WATER BALANCE CALCULATIONS
FOR
COBOCONK, ONTARIO
UNDER AVERAGE CONDITIONS

MONTH	MEAN TEMP. °C	MEAN PRECIPI- TATION mm	ACTUAL EVAPO- TRANSPIRATION mm	ACTUAL WATER BALANCE mm
JAN	-9.2	73.7	0	74
FEB	-8.6	62.5	0	63
MAR	-2.9	68.9	0	69
APR	5.3	73.4	29	44
MAY	11.9	67.6	77	-9
JUN	17.0	86.4	107	-21
JUL	19.4	79.6	107	-27
AUG	18.4	85.6	97	-11
SEP	14.3	77.6	75	2
OCT	8.3	65.4	39	26
NOV	1.7	92.8	6	86
DEC	-6.3	75.9	0	76
YEAR		909	537	372

FIGURE 7






FIGURE 8





6.0 GROUND WATER USE


The following tasks were completed in order to assess ground water use in the vicinity of the closed Coboconk Landfill:

- a) MOE Water Well Log Computer Printouts for the area were reviewed and plotted (see Appendix II).
- b) Copies of the original MOE water well logs for Concession RFC lots 33, 34, 35 and 36 were obtained, reviewed and plotted (see Appendix II).
- c) The Victoria County Official Plan Volume 1 Physical Base report was reviewed.
- d) A water well survey involving resident interviews at eight homes near the landfill was carried out in August, 1988 (see Appendix II).

The water wells (H1 to H8) included in the survey are plotted on Figure 6. MOE well numbers are also provided where possible. There is some uncertainty regarding the locations of some of the wells recorded by the MOE due to the poor quality of the well location maps provided by the drillers.


The Victoria County Official Plan indicates that the Village of Coboconk uses individual wells for water supply. Sewage works consist of holding tanks and septic tank disposal systems. According to this report about 84% of the wells in this area are completed in bedrock and the rest in overburden. The limestone bedrock is geologically mapped as the Bobcaygeon and Gull River Formations and is by far the most important aquifer. Most wells obtain good yields and the limestone aquifer is an important water supply resource for future development in Coboconk and the surrounding area.

This assessment was confirmed during a detailed review of the thirteen original water well records for Concession RFC Lots 33, 34, 35 and 36. All the wells are completed in the limestone bedrock except for one shallow overburden well. Well depths range from



6 to 35 m with an average depth of 20 m. Reported static water levels range from 1 to 17 m with an average level of 7 m. Specific capacities vary between .01 and 0.5 L/s/m with an average of about 0.17 L/s/m, which confirms that yields are adequate for residential purposes.

Three of the residents which were interviewed reported problems with their wells. Well H7 was partially depleted of water about four years ago apparently due to ground water interference effects from expansion of the Cedarhurst Quarry. A new well will reportedly be drilled soon. Well H8 apparently has been flooded in the past by spring runoff. Well H6 was apparently contaminated with petroleum from a leaking tank at the Texaco Station on Highway 35. Water was brought in for the resident's use for three years, during which time the well was pumped out and apparently rehabilitated.



7.0 GROUND WATER FLOW


Ground water levels were measured in the on-site monitors on five occasions in August and on one occasion in November 1988. These results and geodetic water level elevations calculated from survey information are presented in Appendix III.


The water table measured in the monitors at the site generally occurred between 2 and 7 m below grade in August, depending upon location. The summer of 1988 was exceptionally hot and dry which probably accounts for the deep water levels at monitor locations 2, 3 and 4 in August. The water table in November, after a period of heavy rain, was between 0 and 3.5 m below grade, depending upon location.

Water level rises in the order of 0.8 to 5.5 m occurred in the various monitors between August and November. The smallest changes occurred at borehole 1. Highly permeable fractures are present in the upper 2 m of borehole 1 as evidenced by excessive water losses during coring of the bedrock at this location. These permeable fractures probably control water levels at borehole 1 within a narrow range by rapidly draining off any excess infiltration.

Water levels in all the other monitors at borehole locations 2, 3 and 4 rose by 3.5 m or more between August and November 1988. The magnitude of these water level rises is due to the relatively low fracture porosity of the limestone bedrock. For instance, if the effective fracture porosity was 1% then a 10 mm infiltration event transferred to the water table could cause a 1 m rise in ground water levels.

Figures 9 and 10 present water table elevation maps for August 25 and November 11, 1988 based on water level elevations in on-site ground water monitors. A surveyed water level elevation in the Cedarhurst Quarry drainage ditch and an estimated water level for the Gull River (estimated from 1:50,000 topographic map) are also provided on Figures 9 and 10 to illustrate how ground water elevations at the landfill site relate to the regional ground water flow system.





Legend

- PROPERTY BOUNDARY
- ESTIMATED EXTENT OF REFUSE
- 276.61 WATER TABLE ELEVATION (mASL) MEASURED NOV. 11, 1988
- INFERRED GROUND WATER FLOW DIRECTION

AERIAL PHOTOGRAPHY - 1978

SCALE 1:2000

WATER TABLE
ELEVATIONS
(Nov. 11, 1988)

Figure
10



Ground water flow was to the north-northwest on both dates, in spite of the large seasonal changes in water levels. Flow to the north-northwest suggests that ground water flow below the landfill is influenced by the dewatering effect of the Cedarhurst Quarry as well as by the Gull River which is probably a regional ground water discharge zone.

Lateral hydraulic gradients generally range between 0.03 and 0.08 with the higher lateral gradients occurring in August. Lateral hydraulic gradients in November were less than half of what they were in August. In addition the lateral gradients appear to be slightly steeper at the south end of the site near the bedrock scarp and tend to flatten out on the flat limestone plain north of the landfill.

Vertical hydraulic gradients at this site are generally downward indicating recharge conditions, as would be expected in this uplands area. In August the vertical hydraulic gradients were between 0.02 and 0.18 downward. In November they were reduced to an average of about 0.01 downward.

All the on-site ground water monitors were slug tested to assess the in-situ hydraulic conductivity of the fractured limestone bedrock. The test results were plotted and analyzed using the methods of Hvorslev (1952). The test plots and calculations are presented in Appendix III. The hydraulic conductivity results are summarized below in Table 2.


The measured hydraulic conductivity of the limestone bedrock ranged from 9×10^{-9} to 1×10^{-5} m/s with a geometric mean value of 3×10^{-7} m/s and a median value of 2×10^{-7} m/s. Hydraulic conductivity values vary over three orders of magnitude due to the presence or absence of fracture as well as variations in fracture aperture and continuity. The primary hydraulic conductivity of the unfractured limestone matrix at this site is probably less than 1×10^{-8} m/s.

It is difficult to estimate average ground water flow velocities in fractured bedrock due to the large variability in hydraulic conductivities from place to place. However, based

Closed Coboconk Landfill 88-237

Table 2 Summary for Hydraulic Conductivity of the
Limestone Bedrock Based on Slug Test Results

Monitor	Depth of Screen (m)	Hydraulic Conductivity (m/s)
1-I	8.3 - 9.8	1×10^{-5}
1-II	3.1 - 6.1	1×10^{-7}
2-I	7.5 - 9.0	8×10^{-6}
2-II	1.6 - 4.6	9×10^{-9}
3-I	7.2 - 8.7	1×10^{-8}
3-II	1.3 - 4.3	2×10^{-7}
4-I	5.8 - 8.8	6×10^{-7}



on an average hydraulic gradient of 0.055, the geometric mean hydraulic conductivity of 3×10^{-7} m/s and estimated fracture porosity for the limestone of 1%, an average ground water flow rate of about 50 m/yr can be calculated using Darcy's Law. Based on this flow rate, average ground water travel times from the landfill to Gull River (0.5 km) or to the Cedarhurst Quarry (0.4 km) would be in the order of ten years. Since the landfill closed over fourteen years ago there is no reason to expect that leachate impacts will become more severe in the future.



8.0 WATER QUALITY IN GROUND WATER MONITORS

The on-site ground water monitors were developed by removing three well-bore volumes of water prior to sampling. Well development and sampling were carried out using Terraqua hand pumps and polyethylene tubing dedicated to each monitoring well. The samples were collected in August 1988. There was insufficient water in shallow monitors 2-II and 3-II in August so these monitors were developed and sampled in November 1988 after the water table had risen in response to infiltration from a period of wet weather. Monitor 4-I was sampled in August and again in November to provide a preliminary assessment of ground water quality seasonal variations.

The chemical analysis results are presented in Appendix IV and are summarized on Table 3.

Monitors 1-I and 1-II are located upgradient of the landfill and thus are representative of background ground water quality. Monitors 2-I, 2-II, 3-I and 3-II are located downgradient of the landfill where some leachate impacts on ground water quality would be expected. Monitor 4-I was installed directly below the refuse and should have water quality which is representative of the leachate source.

Review of Table 3 indicates the chemical concentrations in the leachate monitor, 4-I, and in the downgradient monitors, 2-I, 2-II, 3-I and 3-II, are generally not much higher than the background concentrations in monitors 1-I and 1-II. Water quality in all the monitors is relatively good compared to typical landfill sites. The leachate is exceptionally dilute. For instance the maximum chloride concentration measured on-site is 11 mg/L. The drinking water objective is 250 mg/L and it is not uncommon to get chloride concentrations of 1000 mg/L or more in leachate from typical Ontario landfills.

The leachate sample from monitor 4-I was also tested for a scan of volatile organic compounds (U.S. EPA Method 624), phenols and heavy metals. No volatile organic compounds were detected at concentrations above the method detection limits.

PROJECT NO: 88-237 CLOSED COBOCONK LANDFILL

TABLE 3: Summary of Water Quality in Ground Water Monitors
Results in mg/L unless otherwise noted.

MONITOR	1-I	1-I(BH6)	1-II	2-I	2-II	3-I	3-II	4-I	4-I	Municipal Tap (BH5)
DATE	Aug-88	Aug-88	Aug-88	Aug-88	Nov-88	Aug-88	Nov-88	Aug-88	Nov-88	Aug-88
PARAMETERS										
Total Dissolved Solids	314	215	290	297	396	315	769	323	576	158
Conductivity (μ mho/cm)	625	430	575	560	522	660	1098	640	766	300
Calcium	113	75	99	64	64	86	137	88	117	36
Magnesium	3.8	3.6	7.8	14	5.7	12	14	21	10	8.3
Sodium	0.9	0.6	0.9	20	25	7.6	25	4	3.3	8.8
Potassium	0.6	0.4	3.5	3.7	2.1	6.3	23	3.4	11	1.2
Chloride	2	2	3	11	3	11	10	4	1	25
Alkalinity (CaCO ₃)	290	195	250	175	199	190	294	280	321	85
Sulphate	15	11	21	70	49	70	176	26	33	26
Iron (dissolved)	0.07	0.04	0.02	0.03	0.03	0.06	0.03	0.05	0.02	0.02
Manganese (dissolved)	0.06	0.06	0.04	0.04	0.03	0.03	0.04	0.04	0.06	0.01
Ammonia (N)	<.05	<.05	<.05	0.4	<.05	0.25	<.05	0.23	0.09	0.19
Nitrate+Nitrite (N)	<.05	<.05	<.05	0.86	0.22	0.56	4.6	0.11	0.74	0.24
Total Organic Carbon	4.1	3.5	2.9	4.1	2.0	5.4	5.6	2.6	2.0	2.6
Phenols	<.002	<.002	<.002	0.006	<.002	0.003	<.002	0.003	<.002	0.003

1-I(BH6) - 'Blind' Replicate Sample

Toronto Tap (BH5) - 'Blind' QA Sample



Similarly the leachate heavy metal concentrations were generally below detection limits or were typical of background levels in ground water. Phenol concentrations slightly exceeded the drinking water limit in the August leachate sample and several downgradient monitors, however, phenols were not detected in the November samples from monitors 2-II, 3-II and 4-I.

The dilute nature of the leachate and the lack of significant ground water quality degradation can probably be attributed to the following:

- (a) the landfill is very small,
- (b) landfill closed over fourteen years ago,
- (c) the most of the refuse was burned, and
- (d) the landfill does not have an impermeable cover and infiltrating precipitation has probably flushed out most of the soluble contaminants years ago.

Ground water quality data from monitoring wells and residential wells were compared to the Ontario Drinking Water Objectives. The results of this comparison are presented in Table 4. None of the health-related objectives were exceeded in any of the monitoring wells. Only four of the aesthetic consideration objectives were exceeded and only in a few of the monitoring wells.


Replicate samples were collected in August from monitor 1-I, residential well H6 and surface water station R2. The replicate samples were submitted to the laboratory with false names (BH6, H9 and R3) for quality assurance purposes. The results of the residential well (H6/H9) and surface water (R2/R3) replicates correlate reasonably and are generally within the accepted range for laboratory accuracy. The replicate samples from ground water monitor 1-I do not correlate as well but this is more likely related to sampling than to laboratory analysis. The residential well and surface water replicate samples were collected at the same time. However, it was necessary to allow water levels in monitor 1-I to recover for several hours prior to collecting the second sample.

PROJECT NO: 88-237 CLOSED COBOCONK LANDFILL

TABLE 4: Drinking Water Objectives Exceedances

Parameter	MOE Drinking Water Objectives	Residential Wells in Exceedance (concentrations in mg/L)	Monitoring Wells in Exceedance (concentrations in mg/L)
Chloride	250	H6 (360)	
Total Dissolved Solids	500	H1 (877), H3 (606), H4 (590), H6 (999)	3-II (769), 4-I (576 Nov)
Total Organic Carbon	5.0	H7 (5.9)	3-I (5.4), 3-II (5.6)
Iron*	0.3	H1 (.31), H5 (.36), H6 (.64), H7 (1.0)	
Manganese*	0.05	H3 (.16), H6 (.46), H7 (.11)	1-I (.06), 4-I (.06 Nov)
Phenols	0.002	H3 (.006), H5 (.003), H6 (.003) H7 (.003), Toronto Tap (BH5) (.003)	2-I (.006), 3-I (.003), 4-I (.003 Aug)

* total metal concentrations were considered for residential wells and dissolved metal concentrations were considered in monitoring wells due to the presence of suspended silt and clay particles.



9.0 WATER QUALITY IN RESIDENTIAL WELLS

Water samples were collected from eight residential wells in the vicinity of the landfill in August 1988. Residential well sampling locations are shown on Figure 6. The taps were allowed to run for several minutes prior to sampling, while the residents were being interviewed about their wells (see Appendix II).

The chemical analysis results are presented in Appendix IV and are summarized in Table 5. Table 4 (see section 8.0) presents the results of a comparison of the data with Ontario Drinking Water Objectives. No health-related objectives were exceeded.

Four of the residential wells (H1, H3, H4 and H6) which are located along Highway 35, have above background levels of conductivity ($>1,000$ umho-cm) sodium (>50 mg/L) and chloride (>50 mg/L), and exceed the objective for total dissolved solids (T.D.S.). This is probably due to application of de-icing salt to the highway, parking lots and driveways. Well H6 also exceeded the objective for chloride of 250 mg/L.

Four wells exceeded the limits for total iron and three exceeded the total manganese limit. These aesthetic limits are established primarily to prevent staining of plumbing fixtures and the levels of iron and manganese found could be caused by natural background water quality. One well (H7), also slightly the aesthetic objective for total organic carbon, and four wells (H3, H5, H6 and H7) exceeded the aesthetic objective for phenols as did the quality assurance blank sample of municipal tap water.

Three wells H3, H4 and H8 have above-background nitrate concentrations (2.2 to 5.2 mg/L) although the drinking water objective of 10 mg/L was not exceeded. This suggest minor ground water quality degradation from septic systems, which is common where fractured bedrock occurs near surface as it does in this area.

Three of the residents interviewed reported water quality problems with their wells. Well H6 was reportedly contaminated with petroleum product from a spill at the nearby Texaco station several years ago. Apparently the resident had to import water for three years. During this time the well was pumped out and rehabilitated, and since then the


PROJECT NO: 88-237 CLOSED COBOCONK LANDFILL

TABLE 5: Summary of Water Quality in Residential Wells
Results in mg/L unless otherwise noted.

Residential Well	H1	H2	H3	H4	H5	H6	H6(H9)	H7	H8	Municipal Tap (BH#5)
Date	Aug-88	Aug-88	Aug-88	Aug-88	Aug-88	Aug-88	Aug-88	Aug-88	Aug-88	Aug-88
Parameters										
Total Dissolved Solids	877	300	606	590	380	999	985	422	387	158
Conductivity ($\mu\text{mho/cm}$)	1480	593	1240	1128	760	1960	1990	770	760	300
Calcium	138	88	129	134	94	200	197	112	111	36
Magnesium	24	11	13	8.3	20	9.8	9.7	13	6.6	8.3
Sodium	120	7.3	84	58	14	170	160	22	16	8.8
Potassium	5.0	1.9	3.4	1.9	4.1	3.7	3.7	3.0	2.4	1.2
Chloride	54	8	140	95	22	360	350	41	20	25
Alkalinity (CaCO_3)	210	240	280	230	250	350	360	250	230	85
Sulphate	400	33	49	140	67	35	34	75	65	26
Iron (total)	0.31	0.05	0.19	0.03	0.36	0.64	0.64	1.0	0.03	0.03
Manganese (total)	0.05	0.01	0.16	0.01	0.05	0.46	0.45	0.11	0.01	<.01
Ammonia (N)	0.35	<.05	<.05	<.05	0.19	0.93	0.95	0.14	<.05	0.19
Nitrate+Nitrite (N)	<.05	0.13	2.9	2.2	0.17	0.69	0.73	<.05	5.2	0.24
Total Organic Carbon	1.7	2.6	3.9	2.8	4.1	4.5	4.5	5.9	3.3	2.6
Phenols	<.002	<.002	0.006	<.002	0.003	0.003	<.002	0.003	<.002	0.003

H6 (H9) - 'Blind' Replicate Sample


Toronto Tap (BH#5) - 'Blind' QA Sample



resident has resumed use of the well. The owner of well H8 reported that flooding of the well during spring run-off was a problem in the past. The owner of well H7 reported sulphur problems and water level depletion which she attributed to the dewatering effect of the nearby Cedarhurst Quarry.

Based on the available data it seems unlikely that leachate from the closed Coboconk Landfill will ever have a detectable impact on the residential wells in the area. While it is hydraulically possible for leachate to reach some of the residential wells the leachate would likely have negligible impact because:

- (a) The leachate chemistry at this landfill is so dilute that concentrations of most parameters are not as high in leachate as they are in water from local residential wells.
- (b) Dilution and attenuation of leachate would occur along the 200 m long flow path to the nearest residential wells.
- (c) The effects of dilute leachate impact would be masked by potential impacts of local contaminant sources such as septic systems and road salt contamination which are located nearer the residential wells




10.0 SURFACE WATER FLOW

No streams or flowing surface water were observed on the landfill property during site visits in August and November 1988, although some ponded surface water was present in November.

The ditch which drains the Cedarhurst Quarry, north of the landfill property, was flowing in August, 1988 after an exceptionally dry summer. This observation confirms that this drainage ditch is fed by ground water discharge.

The Gull River is the area's major drainage channel and is located about 500 m from the landfill. Stream flow data for the Gull River is available from the gauging station (No. 02HF002) at Norland, 8 km north of Coboconk. Mean annual discharge at this station was $30.4 \text{ m}^3/\text{s}$ for the period 1963 to 1986. The highest daily discharge for the period of record was $80.4 \text{ m}^3/\text{s}$ which occurred on April 2, 1976. The lowest daily discharge was $1.37 \text{ m}^3/\text{s}$ which occurred on December 22, 1964.



11.0 SURFACE WATER QUALITY

Samples of surface water from the Gull River (R2, R3, R4) and the Cedarhurst Quarry drainage ditch (Q1) were collected in August, 1988. A sample of ponded surface water (SWA) was collected near the west side of the landfill in November, 1988. Chemical analysis results of these samples are provided in Appendix IV and are summarized in Table 6.

Water quality in the Gull River is good. Due to the large flow volumes in this river, it would be impossible to ever detect any leachate impacts attributable to the closed Coboconk Landfill.

The water used for coring the boreholes at the landfill was obtained from the Gull River at location R2.

The water quality in the quarry ditch is much more mineralized than the Gull River water due to ground water discharge from the limestone bedrock. Concentrations of conductivity, calcium, magnesium, sodium, alkalinity and sulphate are up to an order of magnitude higher than in the Gull River.

Water quality in ponded surface water near the west flank of the landfill also contained elevated levels of conductivity, calcium, and alkalinity which are not typical of runoff from recent precipitation. However, the chloride concentration for SWA was <1 mg/L which is not typical of leachate contamination. SWA is located near monitors 2-I and 2-II. The water table was observed to be at surface in these monitors in November 1988 which suggests that the mineralized water quality in the SWA sample may be related to localized ground water discharges from the fractured limestone outcrops in this area at the base of the bedrock scarp.

PROJECT NO: 88-237 CLOSED COBOCONK LANDFILL

TABLE 6: Summary of Surface Water Quality
Results in mg/L unless otherwise noted.

Station	Q1	R2	R2(R3)	R4	SWA	Municipal Tap (BH#5)
Date	Aug-88	Aug-88	Aug-88	Aug-88	Nov-88	Aug-88
Parameters						
Total Dissolved Solids	384	40	40	35	500	158
Conductivity (μ mho/cm)	740	73	76	65	570	300
Calcium	82	9	9	8	104	36
Magnesium	18	1.8	1.7	1.7	3.0	8.3
Sodium	15	1.5	1.8	1.3	10	8.8
Potassium	3.7	0.7	0.6	0.5	4.0	1.2
Chloride	19	3	3	3	<1	25
Alkalinity (CaCO ₃)	140	19	21	16	294	85
Sulphate	150	11	10	10	18	26
Iron (total)	0.07	0.07	0.30	0.04	0.03	0.03
Manganese (total)	0.01	0.02	0.05	0.01	0.04	0.01
Ammonia (N)	0.1	0.05	<.05	<.05	<.05	0.19
Nitrate+Nitrite (N)	2.5	<.05	<.05	<.05	<.05	0.24
Total Organic Carbon	4.7	4.6	4.2	4.1	3.7	2.6
Phenols	<.002	<.002	<.002	<.002	-	0.003

R2 (R3) - 'Blind' Replicate Sample

Toronto Tap (BH #5) - 'Blind' QA Sample



12.0 LANDFILL GAS


Methane and carbon dioxide are the principal gases generated at a landfill site. Carbon dioxide is heavier than air and is not explosive. Methane is a combustible gas which is explosive in concentrations of 5 to 15% mixed with air. Methane is lighter than air and tends to migrate upward.

Lateral off-site gas migration problems generally occur when frozen ground surfaces or low permeability landfill covers prevent upward venting of gas to the atmosphere. When this occurs, gas pressure builds up in the landfill and the gas begins to migrate laterally towards areas of low pressure, such as underground spaces like basements. Winter operation of furnaces in basements of nearby buildings can actually cause a negative pressure sink that induces gas flow towards it. A layer of unsaturated, permeable soil or rock that is horizontally continuous is generally required for significant gas movement to occur. Methane cannot move through saturated soils or rock (e.g., below the water table) and only moves very slowly through low permeability materials.

Six hand auger boreholes were drilled into the top of the landfill to permit gas sampling and testing in August, 1988. Hand auger borehole locations are shown on Figure 6 and geologic logs are presented in Appendix III.

Methane gas concentrations were measured in each hand auger borehole using a portable gas sniffer which detects combustible gases as a percentage of total atmosphere. No combustible gas concentrations were detected in any of the hand auger boreholes. Similarly, there was no evidence of vegetation damage caused by methane gas concentrations.


The lack of methane gas is consistent with what we know about this landfill. The refuse was burned regularly which would have consumed and oxidized most of the organic matter in the refuse which is the major source of methane production in most municipal landfills. In addition, the landfill surface final cover consists of a thin layer of silty sands with exposed refuse along the northern slope, thus any methane produced would easily



vent to the atmosphere. The site has been closed for over fourteen years so gas generation rates would probably be significantly less than when the site was in operation.

The limestone bedrock occurs from 0 to 0.5 m below grade at this site. Consequently all the refuse was emplaced above grade and there is little likelihood for lateral, subsurface gas migration. In addition, the effective porosity and permeability of the limestone is relatively low, which further restricts subsurface gas movement.

In summary, methane gas impacts from the Closed Coboconk Landfill on adjacent properties and residences is highly unlikely.




13.0 CONCLUSIONS

The following conclusions are drawn based on the results of this hydrogeological assessment and review of previous investigations:

1. The limestone bedrock aquifer which outcrops in the vicinity of the landfill is the main water supply for the residents of this area. Ground water flow beneath the landfill is to the north-northwest towards several residences which are located about 200 m from the landfill. However, the results of this study indicate that the landfill has almost negligible impact on ground water quality in the bedrock aquifer because the leachate is exceptionally dilute. This is probably due to the following factors:
 - (a) the landfill is very small (0.5 hectares),
 - (b) the landfill was closed over fourteen years ago and time has reduced the strength of the leachate,
 - (c) the refuse was burned regularly which reduced the organic content of the leachate, and
 - (d) the leachate is diluted by clean ground water flowing below the site in the limestone bedrock.


There are no detectable water quality impacts on local residential wells attributable to the landfill because of the dilute nature of the leachate and additional dilution and attenuation along the 200 m ground water flow path. Based on our understanding of the landfill history and ground water flow system, any leachate impacts on the bedrock aquifer would have been at a maximum in the 1970s. There is no reason to expect that leachate impacts will become worse in the future.

2. The nearest flowing surface water courses to the landfill are the Gull River, 500 m to the west, and a drainage ditch in the bottom of the Cedarhurst Quarry,



400 m to the north. No leachate impacts were detected on water quality in either of these two streams and none are expected in the future.

3. No methane gas was detected in six hand auger holes drilled into the landfill. There is very little potential for significant off-site methane gas migration in this hydrogeological setting and gas impacts on adjacent residences either now or in the future are highly unlikely.



14.0 RECOMMENDATIONS

Based on the conclusions of this hydrogeological assessment the following recommendations are submitted for consideration:

1. No remedial measures are required at this site to contain or control leachate or methane gas. Improvements to the landfill final cover including covering the exposed refuse along the north face was previously recommended by the MOE in the early 1970s. This would have been a good idea in the 1970s, however, completion of this work in 1989 would undoubtedly involve the destruction of mature trees and vegetation which now cover the site. Since the site is far removed from public view and most of the contaminants in the landfill have already been leached out, it is our opinion that remedial actions to improve the landfill cover would have little beneficial effect at this time.
2. On-site monitoring of ground water and surface water quality, and methane gas is not warranted because the existing impacts are negligible at present and are expected to decrease in the future. Monitoring of residential wells as a landfill-related program is also unwarranted because water quality in the residential wells is far more likely to be affected by nearby septic systems, road salting and other closer contaminants sources than by the landfill. This surficial bedrock aquifer is susceptible to contamination and perhaps the residents should be informed of existing MOE and local Health Department services regarding domestic water well quality.
3. The construction of new residences and water supply wells closer to the landfill than the existing residential wells is probably not advisable without a more detailed investigation of leachate pathways in the limestone aquifer.



15.0 SELECTED REFERENCES

Chapman, L.J., and Putnam, D.F. 1972:

The Physiography of Southern Ontario; University of Toronto Press,
Toronto, Ontario, 386 p.

Finamore, P.F., and Bajc, A.F. 1983:

Quaternary Geology of the Fenelon Falls Area, Southern Ontario;
Ontario Geological Survey, Preliminary Map P.2596.

Hvorslev, M.J. 1951:

Time Lag and Soil Permeability in Ground water Observations. U.S.
Army Corps Engineers. Waterways Exp. Sta. Bull. 36, Vicksburg, Miss.

Liberty, B.A. 1963:

Geology of Tweed, Kaladar and Bannockburn Map-Areas, Ontario.
Geological Survey of Canada Paper 63 - 14, 15 p.

Ontario Ministry of the Environment. 1984:

Water Management. Goals, Policies, Objectives and Implementation
Procedures of the Ministry of the Environment. 70 p.

Thornthwaite, C.W., and Mather, J.R. 1957:

Instructions and Tables for Computing Potential Evapotranspiration and
the Water Balance. Drexel Institute of Technology, Centerton, New
Jersey, 311 p.

Victoria County Planning Department. 1975:

Victoria County Official Plan, Background Studies, Volume 1 Physical
Base. 293 p.

APPENDIX I

MOE FILE INFORMATION



APPLICATION FOR A CERTIFICATE OF APPROVAL FOR A WASTE DISPOSAL SITE

TO: THE DEPARTMENT OF ENERGY AND RESOURCES MANAGEMENT
880 Bay Street,
Toronto, Ontario

To be submitted through Regional
Waste Management Engineer

(1) Under the Waste Management Act, 1970 and the regulations, this applica-

tion is made by Township of Sonerville
Kenmorent, Ont.

Owner of Facility

Address

(2) for the Renewal of a Certificate of Approval for a

Delete item inapplicable

Type of Disposal

Full particulars of Location

(3) located Part lots 35 & 36 First Range
Sonerville Township


(4) A Certificate of Approval No. 321603 for this
Provisional Certificate site was issued Mar. 17 19 71

Delete item inapplicable

(5) No change in use, operation, or ownership of the site has occurred since the date of the original application.

Dated this Oct. 27 day of October 19 71

Mrs. Byrne
Signature of Applicant



(6) The following changes in use, operation or ownership (have occurred since the date of the original application) (are proposed)

have kept burned & buried
every two weeks
Continued on Attached Sheets ☐

Delete item inapplicable

If necessary, provide additional details on separate sheets and attach to application.

(7) The site will be operated in accordance with The Waste Management Act, 1970 and the regulations by George Reese

Name of Operator

Address

The required supporting information to the application is appended hereto.

(8) Notice of this application has been published in the

on and

19 and a copy of the notice is attached.

(9) A certificate that the site does not contravene any of the by-laws of the municipality is attached.

To be completed if applicant is other than a municipality

See notes on sections 1 to 9 on back of last copy (pink) which is to be retained by Applicant.

HALIBURTON, KAWARTHA, PINE RIDGE DISTRICT HEALTH UNIT

Charlotte M. Horner, B.A., M.D., D.P.H. - Medical Officer of Health

Inspection Report
General Sanitation

Date Received Date of Inspection Feb. 12, 1971

Address of Premises: Part of Lots 35 & 36, Front Range - Somerville Twp.

Type of Premises: Refuse Disposal Site.

Tenant P.O. Address

Owner: Twp. of Somerville P.O. Address: Kinmount.

Complainant P.O. Address

Reason for Inspection: Routine

REPORT This site is an open face dump serving the Village of Coboconk (Pop. 800) and surrounding area. Residents of Bexley Twp. also use this dump.

Observations: The dump face measures about 75' x 150'

There is little or no solid cover over rock in this general area and it is suspected that this is the case at the dump site although snow cover made it difficult to determine. Supposedly the dump is heavily infested with rats according to the clerk of Bexley Twp., although none were observed during the inspection. The dump is accessible year round. The nearest dwelling is situated about 1/4 mile away on the corner of the township road and the access road. The nearest watercourse is the Gull River about 1 mile away.

Comment: Mainly because of the lack of soil cover over rock and the difficulty encountered in drawing in fill to cover the refuse, the site is unsatisfactory.

Recommendation: Provisional certificate be issued with a time for expiry.

INSPECTOR *M.D. Dawson*
M.D. Dawson, C.P.H.I. (C)

(OVER)

RECOMMENDATION OF REGIONAL ENGINEER

NOTE: This form shall be submitted by the Regional Engineer to Head Office along with the application form and all supporting information.

(1) DATE APPLICATION RECEIVED: January 18, 1971 File: A 3216

(2) APPLICANT: Township of Somerville

(3) ISSUE: Certificate of Approval ☐

Provisional Certificate of Approval ☒

(4) TIME: Provisional Certificate to Expire in 1 months from date of issue.

(5) CONDITIONS OF ISSUE:

1) SUPPORTING INFORMATION FORM TO BE COMPLETED BY THE MUNICIPALITY & FORWARDED TO THIS OFFICE BY EXPIRY DATE.

(6) DO NOT ISSUE: REFUSE APPLICATION ☐

REVOKE (Cert. No.) ☐

(7) REASONS FOR (6)

(8) DEFER: CIRCULATE TO:

FOR:


(9) DATE: FEB. 17/71 SIGNED: *[Signature]*

Regional Engineer



Department of Energy and Resources Management
Waste Management Branch

APPLICATION FOR A CERTIFICATE OF APPROVAL
FOR A WASTE DISPOSAL SITE



TO: THE DEPARTMENT OF ENERGY AND RESOURCES MANAGEMENT
830 Bay Street,
Toronto, Ontario

To be submitted through Regional
Waste Management Engineer

(1) Under the Waste Management Act, 1970 and the regulations, this applica-

tion is made by Township of Simcoeville
Kirkfield Ontario

Owner of Facility

Address

(2) for the Renewal of a Certificate of Approval for a

Delete item inapplicable

Type of Disposal

(3) located Part of lots 35 & 36 Front Range
Simcoeville Township

Full particulars of Location

(4) A Certificate of Approval No. _____ for this
Provisional Certificate site was issued _____ 19 _____

Delete item inapplicable

(5) No change in use, operation, or ownership of the site has occurred since
the date of the original application.

Dated this 18th day of Nov, 19 70

Musa Galattman
Signature of Applicant

(6) The following changes in use, operation or ownership (have occurred
since the date of the original application) (are proposed)

Delete item inapplicable

If necessary, provide additional
details on separate sheets and attach
to application.

have kept burned & buried
about every 2 weeks

Continued on Attached Sheets ☐

(7) The site will be operated in accordance with The Waste Management Act,
1970 and the regulations by Jacob Gill

Name of Operator

Address

R.R. 1 Kirkfield Ontario

The required supporting information to the application is appended hereto.

(8) Notice of this application has been published in the _____
_____ on _____ and

_____ 19 _____ and a copy of the notice is attached.

(9) A certificate that the site does not contravene any of the by-laws of the
municipality is attached.

To be completed if applicant is other
than a municipality

See notes on sections 1 to 9 on back
of last copy (pink) which is to be
retained by Applicant.

SEE FRONTING INFORMATION
TO AN
APPLICATION FOR APPROVAL
OF A
LANDFILL DISPOSAL SITE

1. Wastes to be Disposed of Comprise

Domestic	60 %
Commercial	25 %
Industrial Waste	3 %
Hauled Liquid Industrial Waste	%
Agricultural Waste	4 %
Hazardous Waste	2 %
Hauled Sewage	%
* Other	6 %
	100%

* Describe

Total $2\frac{1}{2}$ Tons/Day

Population Served 1000

3. Distance to Nearest WatercourseFt.
Distance to Source of Potable WaterFt.
Distance to DwellingFt.
Distance to Public Road 1000 Ft.
Distance to Cemetery 500 Ft.

Total Area of Site 9 Acres
Anticipated Life 2 Years

General Description of Site

Rocky & 2' of dirt on top

5. Proposed Future Land Use

no good for anything

2. Origin and Composition of Principal Components of Waste (other than domestic and commercial)

nil

4. Maximum Depth of Excavation Below Surface

nil Ft

Maximum Height of Fill Above Surface

15 Ft

Type(s) of Material Encountered From Surface

clay loam

2 Ft

Depth of Watertable Below Surface 4 Ft
on 10/1/81 (Date)

6. Operating Equipment

20 hours per month
Bulldozer shovel

Hours of Operation 20 hours per month

7. The Following Documents are Attached

FOR DEPARTMENTAL USE

8. Authorities Consulted:

Health Unit	<input type="checkbox"/> Objection	<input type="checkbox"/> No Objection
O.W.R.C.	<input type="checkbox"/> Objection	<input type="checkbox"/> No Objection
A.M.B.	<input type="checkbox"/> Objection	<input type="checkbox"/> No Objection
Municipality	<input type="checkbox"/> Objection	<input type="checkbox"/> No Objection
Conservation Authority	<input type="checkbox"/> Objection	<input type="checkbox"/> No Objection

Other (See HEALTH UNIT 11/18/81)
BULDOZER

Inspection Record Forms Attached

Commercial	22%
Industrial Waste	3%
Hauled Liquid Industrial Waste	%
Agricultural Waste	4%
Hazardous Waste	2%
Hauled Sewage	%
* Other	6%
	100%

Describe.....

Total..... $2\frac{1}{2}$ Tons/Day

Population Served..... 1000

3. Distance to Nearest Watercourse Ft.
 Distance to Source of Potable Water Ft.
 Distance to Dwelling Ft.
 Distance to Public Road 1000 Ft.
 Distance to Cemetery 5180 Ft.

Total Area of Site 9 Acres
 Anticipated Life 2 Years

General Description of Site

Rocky & 2' of dirt on top

4. Maximum Depth of Excavation nil Ft.
 Below Surface nil Ft.
 Maximum Height of Fill 15 Ft.
 Above Surface 15 Ft.
 Type(s) of Material Encountered From Surface

clay loam 2 Ft.

..... Ft.

..... Ft.

Depth of Watertable Below Surface 4 Ft.
 on n.d. 1 (Date).

5. Proposed Future Land Use

no good for anything

6. Operating Equipment

20 hours per month
 Bulldozer shovel

Hours of Operation..... 20 hours per month

The Following Documents are Attached

FOR DEPARTMENTAL USE

8. Authorities Consulted:

Health Unit	<input type="checkbox"/> Objection	<input type="checkbox"/> No Objection
O.W.R.C.	<input type="checkbox"/> Objection	<input type="checkbox"/> No Objection
A.M.B.	<input type="checkbox"/> Objection	<input type="checkbox"/> No Objection
Municipality	<input type="checkbox"/> Objection	<input type="checkbox"/> No Objection
Conservation Authority	<input type="checkbox"/> Objection	<input type="checkbox"/> No Objection

Other (SEE HEALTH UNIT INSPECTION REPORT) (SECRET)

Inspection Record Forms Attached

Regional Engineer's Report Attached ☐

RECOMMENDATION

SEE FORM 2-11

DATED March 3/71

SIGNED Maurice Station

DATED MAR 8/71

SIGNED P. Station

RECOMMENDATION OF REGIONAL ENGINEER

NOTE: This form shall be submitted by the Regional Engineer to Head Office along with the application form and all supporting information.

(1) DATE APPLICATION RECEIVED: October 29, 1971 File: A. 321603

(2) APPLICANT: Township of Somerville
Pt. Lots 35, 36 Front Range

(3) ISSUE: Certificate of Approval ☐

Provisional Certificate of Approval ☒

(4) TIME: Provisional Certificate to Expire in 8 months from date of issue.

(5) CONDITIONS OF ISSUE:

- 1) ALL OPEN FACES TO BE PROPERLY GRADED, COMPACTED, & COVERED WITH AT LEAST TWO (2) FT. OF FILL
- 2) COMPLETE COVERAGE OF ALL REFUSE TO BE CARRIED OUT AT LEAST WEEKLY
- 3) RST CONTROL PROGRAM TO BE INITIATED.
- 4) SITE TO BE ATTENDED DURING ALL OPEN HOURS & ADEQUATE GATES, FENCING, & SIGNS TO BE INSTALLED.

(6) DO NOT ISSUE:

REFUSE APPLICATION ☐

REVOKE (Cert. No.) ☐

(7) REASONS FOR (6)

(8) DEFER: CIRCULATE TO:

FOR:



ONTARIO

DEPARTMENT OF ENERGY AND RESOURCES MANAGEMENT
WASTE MANAGEMENT BRANCH

TELEPHONE
XXXXXX

XXXXXXXXXXXXX
1 ST. CLAIR AVE. W.

TORONTO

A.321603

FILE REF. No.:

WASTE DISPOSAL SITE
SOMERVILLE TOWNSHIP
LOTS 35 & 36, FRONT RANGE

Report by: P. E. Davidson, P. Eng.,
Regional Engineer,
Midwestern Region,
797 Princess Street,
Kingston, Ontario.

September 7, 1971.

R E P O R T

Report by: Mr. P. E. Davidson, P. Eng.,
Waste Management Engineer,
Mideastern Region,
Waste Management Branch,
Department of the Environment,
797 Princess Street,
Kingston, Ontario.

File No. A.321603

September 7, 1971.

GENERAL:

This site was inspected by the writer on September 1, 1971. It is one of three disposal sites serving the Township, population of which is 1310. (In the main, this site serves Coboconk and surrounding area.)

DETAIL:


The site is located approximately 1 mile south-east of Coboconk, $\frac{1}{4}$ mile east of Highway 35. It is located 250 yds. south of the east-west township road and the same distance from the nearest dwelling which is located at the entrance to the site. The soil type in the vicinity is Dummer loam (shallow phase) over bedrock. There does not appear to be sufficient soil on-site to support a landfill operation. The closest watercourse is the Gull River which is approximately one mile away to the north-west. The site is apparently open at all hours although it was attended when inspected. Although covering has occurred recently on the top, the 12 foot high open sides have not been covered. There are no gates, signs, or fences and some open burning of refuse does take place.

CONCLUSIONS:

- 1) The operation of this site is not in accordance with Ontario Regulation 375/70.
- 2) The location of this site may be found to be unacceptable by the Township when the additional costs of trucking in fill are appreciated.

RECOMMENDATIONS:

- 1) All open faces should be properly graded, compacted, and covered with at least two (2) ft. of fill.
- 2) Complete coverage of all refuse to be carried out at least weekly.
- 3) Site to be attended during all open hours.
- 4) Adequate gates, fencing and signs to be installed.
- 5) Rat control program to be initiated.


P. E. Davidson, P. Eng.

PED/imp



Ontario

Ministry of the
Environment

Waste Management Branch,
880 Bay Street, 3rd Floor,
Toronto, Ontario,
M5S 1Z8.

SITE RESUME

Date: April 27/73

Applicant: Township of Somerville File No. 321603

Location: Pt. lots 35 & 36, Front Range, Somerville Twp.

Common Name (if applicable) Coboconk

Municipalities Served: Somerville Twp.

Population Served 1000 Type of Site Landfill

No. of Inspections: 2 Date of Last Inspection: Mar. 12/73

Upgrading proceeding under an Approved Program: Yes No

Applicant's Attitude: Retarding the Efforts of Branch Adequate

Current Status of Site:

Location:

Acceptable.

Operations:

Operation inadequate.



MINISTRY OF THE ENVIRONMENT

Waste Management Branch,
797 Princess Street,
Kingston, Ontario.
K7L 1G1.

Telephone Area Code 613
546-3297

March 19, 1973.

File No. A.321601
A.321602
A.321603 ✓

Mrs. V. G. Byrne, Clerk,
Township of Somerville,
Kinmount, Ontario.

Re: Waste Disposal Sites
Lot 13, Conc. IV
Lot 1, Conc. XI
Part Lots 35 & 36, Front Range
Somerville Township

Dear Mrs. Byrne:

Routine inspections of these sites were conducted by staff of this Branch on March 12, 1973. The following inspection reports may act as a guide to Council regarding further site maintenance which is required. Please accept these comments as constructive criticism as we consider the action to date by Somerville Township Council to be very positive.

(1) Lot 13, Conc. IV
No. A.321601

This is a small site situated on shallow soil. The site is posted as being closed but no fence or gate has been established to limit access. The cover material applied at the time of closing did not completely cover all refuse. Complete covering of all refuse must be undertaken at the site. Some use of the site since its closing has resulted in a littering problem.

Recommendations:

1. Completely cover refuse with clean fill.
2. Establish a fence to control access to the site.
3. Maintain a litter control program at this site.

- (2) Lot 1, Conc. XI
No. A.321602
(Kinmount)

The site was closed on June 30, 1972. All efforts regarding closing off have been well executed except the total covering of all refuse on site. The dumping area has been compacted and covered but the side face of the dump is still open. Broken glass and rusted steel remain exposed causing a potential hazard to persons entering the site.

Recommendation:

1. Completely cover refuse with clean fill.
- (3) Part Lots 35 & 36, Front Range
A.321603
(Coboconk)

This is the largest of the three sites closed by Somerville Township in 1972. The 12 foot high banks of refuse extend approximately 400 feet along the north and west sides of the site. No successful attempt has been made by the township to properly grade and cover the open sides of the landfill. This requirement for closing off the site was first transmitted to Council in Mr. P. Davidson's report dated September 7, 1971.

The access road has been fenced and a sign noting the new site location has been erected.

Recommendations:

1. That the open garbage face should be reduced to a grade of one foot vertical drop over 3 feet horizontal run.
2. That this 1:3 slope should be compacted and covered with at least two feet of clean fill.

I would be pleased to meet with members of Council to discuss the work required to properly and adequately close the above noted site.

Yours very truly,

F. J. Iliffe

F. J. Iliffe, P. Eng.,
Regional Engineer,
Mideastern Region.

H. Avey/mp

[Handwritten signature]




Department of Energy and Resources Management

PROVISIONAL CERTIFICATE OF APPROVAL
FOR A WASTE DISPOSAL SITE

Certificate No. 321603

Under The Waste Management Act, 1970 and the regulations and subject to the limitations thereof, this Provisional Certificate of Approval is issued to

Township of Somerville,
Kinnaird,
Ontario



for the Landfill Site
located Part of Lots 35 and 36, Front Range, Township of Somerville

subject to the following conditions

1. That all faces including the working face are properly graded, compacted and covered with at least two (2) feet of fill.
2. That all refuse is covered at least once each week.
3. That a rodent extermination and control program is initiated immediately.
4. That the site is supervised during all open hours and that adequate gates, fencing and signs are installed.

This Provisional Certificate expires on the 15th day of July 1972

Dated this 9th day of November 1971



Ministry
of the
Environment
Ontario

INVENTORY OF MOE CERTIFIED WASTE DISPOSAL SITES
(active and closed)

1. Site Identification:

Number: 321603 Name: Cobocok Site

Applicant:

Individual/Business Name: Township of Somerville

Address: P.O. Box 59, Kimmount, Ontario,

Telephone: 1-705-488-2571

Type of Applicant:

Private ☐

Industrial ☐

Municipality ☒

Type of Ownership:

☐ Proprietorship
Name if different than applicant:

☐ Partnership - Name all partners:

☐ Corporation: President's Name -

3. Land Owner: (If not applicant)

Name:

4. Site Location:

Descriptive Location

City ☐

Town ☐

Village ☐

Township ☐

Other ☐

Name: Somerville

Concession: Front Range

Lot Number: 35 and 36

Part of Lot:

Municipality:

Street Address:

Prepared and return location and site plan if not on your record. Note: Include all uses of all adjoining properties.

County Victoria

Electoral District Code 86

MOE Region C

MOE District Peterborough

Has the certificate been registered on title

Yes

☐

No

☒

5. Type of Site:

Organic Soil Conditioning ☐ Transfer ☐ Landfilling ☒ Dump

Describe operations and process to be carried out on site:

Site closed - August 20th, 1974

6. Site Characteristics:

Planning

- a) Present land use Bush.....
- b) Present official plan designation of site Rural
- c) Present zoning category Rural.....
- d) Present land use of all adjoining properties to be provided on location map....
..... Agricultural.....
- e) Distance from any well water supply 750 feet
- f) Nearest water course: a) Name Gull River b) Distance 1 mile

Physical Description

- g) Rate at which site receives waste in (tons/cubic meters) per day..... Site closed
- h) Life expectancy in years based on rate established in (g) N/A
- i) Population served 1,000
- j) Total area of site (hectares) 3.6
- k) Total area approved to be filled (hectares)... N/A completed O not completed
- o) Estimated capacity of site in tons or cubic meters N/A

Hydrogeology

- p) Is there a hydrogeologic report available? Yes _____ No X

Author:

Client:

Date:

Location of report:

- q) Based on a hydrogeologic appraisal by the Ground Water Evaluator

- i) problems with contaminant discharge are likely _____ not likely _____
- ii) problems with contaminant discharge are a reasonable possibility.
Yes _____ No _____
- iii) there are insufficient data to form a reasonable opinion regarding
i) and ii) above X
- iv) priority for further investigation: high _____ low X
reasons: _____

- r) Are the wastes adjacent or near to gravels _____, sands _____, or
bedrock X ?

- s) Is the site in an upland X , or a lowland area?
- t) Is there a ground and/or surface water monitoring program for this site?
Yes No X
- u) Have there been any problems with ground and/or surface water contamination?
Yes No X
- v) Is the nearby ground or surface water presently being used?
Yes 750' Well No
- w) What is the potential use of nearby ground and surface water?
Recreational and Domestic Wells
- x) Has leachate discharge been discussed No ? or calculated No ?

7. Eligible waste categories to be allowed at the site in percent of rate established in 6(g) above:

Domestic

6 0

Industrial

 3 *

Hazardous

 2 *

Others

1 0

Commercial

2 5

Limited to the
class number

101 <input type="checkbox"/>	203 <input type="checkbox"/>	302 <input type="checkbox"/>
102 <input type="checkbox"/>	204 <input type="checkbox"/>	303 <input type="checkbox"/>
103 <input type="checkbox"/>	205 <input type="checkbox"/>	304 <input type="checkbox"/>
104 <input type="checkbox"/>	206 <input type="checkbox"/>	190 <input checked="" type="checkbox"/>
105 <input type="checkbox"/>	207 <input type="checkbox"/>	290 <input type="checkbox"/>
106 <input type="checkbox"/>	208 <input type="checkbox"/>	401 <input type="checkbox"/>
201 <input type="checkbox"/>	209 <input type="checkbox"/>	402 <input type="checkbox"/>
202 <input type="checkbox"/>	301 <input type="checkbox"/>	

601 <input type="checkbox"/>
602 <input type="checkbox"/>
603 <input type="checkbox"/>
604 <input type="checkbox"/>
605 <input type="checkbox"/>
606 <input type="checkbox"/>
607 <input type="checkbox"/>

Describe

Agricultural

.....

.....

.....

.....

.....

.....

.....

* Dry construction material

8. Control System:

Is there any - Gas control system Yes ☐ No ☒

If yes, please describe

- Gas recovery system Yes ☐ No ☒

If yes, please describe

- Leachate on site treatment Yes ☐ No ☒

If yes, please describe

- Leachate off site treatment Yes ☐ No ☒

If yes, please describe

9. Recommendations for Certification:

Conditions:.....
Site is closed and should not be reopened nor certified
.....

Reasons.....

10.Environmental Officer: Name:.....

Signature: Paul Chester

Date this form was completed:..October.19th,.1979.

To be completed by the Environmental Approvals Branch.

11. Examined By:.....Certified correct:.....

Date:

TWSP. OF SOMERVILLE
COBOCONK SITE, L. 35+36, F.R.



BUSH

BUSH

RAVINE

COVERED GARBAGE


BUSH

BUSH

BUSH

TWSP. ROAD

SCRUB LAND



① B. Bant
② Jacques Paul K. or
③ File - Bexley Top? ~~Hinc~~

WM-08-03

May 6, 1986

Township of Bexley
Coboconk, Ontario
KOM 1K0

Attention: Helen Russell
Clerk-Treasurer

Dear Mrs. Russell:

Re: Proposed Sale of Former Landfill Site
Parts of Lots 35 and 36, Front Range
Township of Somerville

In response to your letter of April 25th, 1986, regarding the
aforementioned subject, please be advised that:

(1) our files indicate that the subject property was used as a
landfill site from March 17, 1971, to August 20, 1974.

(2) under Section 45 of the Environmental Protection Act, "No use
shall be made of land or land covered by water which has been
used for the disposal of waste within a period of twenty-five
years from the year in which such land ceased to be used unless
the approval of the Minister for the proposed use has been given.
R.S.O. 1980, c. 141, s. 45, and

(3) it is our feeling that the owner(s) of the subject property
have a moral obligation to inform the prospective buyer of the
previous use of the property, the liabilities, and of the
restrictions for its future use.

It is our understanding that the prospective buyer is Mr. Guy
Mitchell, who plans to use this property to redirect runoff away
from his present property and dwelling. As noted in the
foregoing, any use of the subject property must receive approval
from this Ministry.


-Continued.../2

Helen Russell -2-

With respect to the question of putting the property up for Tender, we suggest that reference be made to the Municipal Act and/or your solicitor.

Should you have any questions regarding this matter, please contact me at this office.

Yours truly,



Clare Muisiner
Environmental Officer
Abatement East Section

CRM:bh

cc: Mr. M.J. McBride





WASTE DISPOSAL SITES (LANDFILL)

Application/Certificate No.

321603

☐

- 1 - Delete
2 - Add or New
3 - Change

If this inventory is for Notification of Changes fill in only the data which is being revised.

1. Site Disposition: Active () Closed (x) Not Approved ()

2. Applicant:

Municipal (x) Provincial () Other ()

Name: Coboconk Site

Address: P.O. Box 59 Postal Code

City/Prov.: Kinmount, Ontario Telephone: 705-488-2571

If Applicant not Municipal or Provincial complete the following:

() Proprietorship
Name, if different than applicant: () Corporation: President's Name:

() Partnership - Name all partners:

(i)

(ii)

3. Land Owner: (if not applicant)

Name:

Address:

4. Lessee (if applicable)

Name:

Address:

5. Site Operator

Name: Jacob Gill

Title:

Address: R.R. #1, Kirkfield, Ontario

6. Site Location:

Municipality Name: Sommerville Township Municipal Code 85

From Plan of Survey:

Mun. Name: Sommerville Township Municipal Code 85

Concession: Front Range

Lot No: 35 and 36

Part of Lot: 35 and 36

Street Address:

7. Geocode

Zone _____ Easting _____ Northing _____

8. Site Characteristics and Waste Category

A. Rate at which site can receive waste per day.

Domestic 60% ☐ Tonnes ☐ Cu. Metres Commercial 25% ☐ Tonnes ☐ Cu. Metres

Liquid Industrial 0 ☐ Tonnes ☐ Cu. Metres Hazardous 0 ☐ Tonnes ☐ Cu. Metres
☐ Litres ☐ Litres

Non Hazardous Solid Industrial 3% ☐ Tonnes ☐ Cu. Metres Other 10% ☐ Tonnes ☐ Cu. Metres

For each Category of Waste List the Class Number as per MOE Classification Guidelines. _____

190

B. Number of days/year the site is open 20 hrs./month

C. Population served 1,000

D. Names of all municipalities/major industries intended to be served by the site

1) Coboconk
2) Sommerville Township
3) _____

4) _____
5) _____

E. Total area of site 3.6 Hectares

F. Total area to be filled n/a Hectares

G. Estimated capacity of the site n/a Tonnes or _____ Cu. Meters

9. Control System

a. Monitoring for - Gas ☐ Yes ☐ No - Ground Water ☐ Yes ☒ No - Surface Water ☐ Yes ☒ No

b. Control system for - Gas ☐ Yes ☒ No - Gas utilization ☐ Yes ☐ No - Leachate ☐ Yes ☐ No

10. Hydrology

Author: _____

Date: _____

b. Hydrogeologic Appraisal by the Ground Water Evaluator:

Author: _____

Date: _____

11. A. Conditions for Certification Yes (x) No ()
B. Has the certificate been registered on title Yes () No (x)
C. Was there a Hearing Held Yes () No (x)
D. Certificate issued by MOE Region () Head Office (x)
12. A. Date Application was completed or changed November 18, 1970
B. Date Original Certificate was issued March 17, 1971
C. Date Waste Site Closed August 20, 1974

This inventory form was completed by: Paul Claster

Approved by Environment Approval Branch for Computer Inventory

Signed _____



Ministry
of the
Environment

Ministère
de
l'Environnement

Central
Region

Région du
Centre

Aug 31/81
(NB) WMB want to study this site as for Ennis more
James Bifford

139 George Street North
Peterborough Ontario
K9J 3G6
705/743-2972

139 nord, rue George
Peterborough (Ontario)
K9J 3G6
705/743-2972

January 14, 1987

To: Brian

From: Paul C.

Re: Closed Landfill Site - Coboconk - 321603
Somerville Township

I spoke with Mike McBride about this site. He didn't have much knowledge about it. However, he informed me the land had been sold to an adjacent landowner, Gilbert Mitchell, in 1986. Mr. Mitchell is aware of the closed site and of the 25 year rule. He uses the land for the storage of wood.

I spoke with Reeve Maurice Watson who reiterated the above. This site was used in conjunction with Bexley Township. This included the plywood company Vic-Ply. As far as the Reeve is aware there was no hazardous waste deposited at this site.

On the original application, dated March 3, 1971, "wastes to be disposed of comprise" should have read Industrial Waste - 5% instead of 3% and 2% hazardous waste.

Due to the nature of the land (lack of adequate soil material), proximity of new homes in the area and the importation of cover material, it is my estimation that a survey of the groundwater be conducted by this office, not W.M.B. I further suggest Derek and Ross be involved with this.

Paul Chater

Environmental Officer
Abatement East Section

PDC:bh

cc: D. Smith/R. Hodgins

File
WMB-08 05



Cedar post-

APPENDIX II

- **MOE COMPUTERIZED WATER WELL RECORDS**
- **MOE ORIGINAL WATER WELL RECORDS**
- **GLL WATER WELL RECONNAISSANCE SURVEY FORMS**

VICTORIA COUNTY 64

MUNICIPALITY CONCESSION ETC	LOT	WELL NO	UTM EASTING NORTHING	ELEV FEET	DATE	DRILLER	CSG DIA INS	KIND OF WATER	WATER FOUND FEET	STAT LVL FEET	PUMP LVL FEET	TEST RATE GPM	TEST TIME HR/MN	WATER USE	OWNER/LUG/SCREEN DEPTHS IN FEET TO WHICH FORMATIONS EXTEND
SOMERVILLE TOWNSHIP (CONTINUED....)															
RFC	28	64- 5281	673887 4944663	850	07/73	2517	6		54	25	50	5	4/20	DO	CRUICKSHANK I BLCK TPSL 0002 GREY CLAY BLDR 0039 GREY LMSN 0054
RFC	28	64- 4412	673910 4944680	850	04/71	2517	6	FR	41	20	20	7	1/00	DO	MAFFY S BRWN CLAY MSND BLDR 0018 BRWN FSND STNS 0041 GREY LMSN 0049
RFC	29	64- 5973	673921 4944775	850	05/74	2517	6	FR	52	20	50	7	2/00	DO	KINSMAN ROBERT BLCK TPSL 0002 GREY LMSN BLDR CLAY 0040 GREY LMSN 0052
RFC	29	64- 7441	673930 4944740	850	09/75	1312	5	FR	20 38	8	22	30	2/00	DO	CARITARI MARCEL BRWN CLAY STNS HPAN 0020 BRWN STNS SAND 0038
RFC	29	64- 5807	674000 4944861	850	06/74	2515	6	FR	45	34	34	8	2/00	DO	CRUICKSHANKS I GREY CLAY STNS 0043 GREY LMSN 0052
RFC	29	64- 5797	674028 4944917	850	08/74	2515	6	FR	30	22	36	5	2/00	DO	BINO A BRWN CLAY STNS 0027 WHIT LMSN SHLE 0032 WHIT LMSN 0039
RFC	29	64- 4577	674050 4944790	850	10/71	2517	6	FR	33	13	35	5	2/00	DO	GORDON T BLDR 0004 CLAY GRVL 0030 LMSN 0040
RFC	30	64- 6979	674080 4945010	850	05/77	2515	6	FR	18	2	18	2	2/00	DO	HOGAN JIM BRWN CLAY STNS 0017 GREY LMSN HARD 0029
RFC	30	64- 5972	674093 4945081	850	10/74	2517	6	FR	26	6	28	4	2/00	DO	LEADBEATER HAROLD BRWN CLAY BLDR 0019 GREY LMSN 0030
RFC	30	64- 2873	674150 4945200	875	09/63	1312	6	FR	51	10	25	15	1/00	DO	THOMPSON G W BLUE CLAY MSND HPAN 0051 LMSN SHLE 0052
RFC	30	64- 3545	674190 4945170	865	05/68	2548	6	FR	36	10	16	4	2/00	DO	KIRWAN G CLAY STNS 0030 LMSN 0036
RFC	31	64- 2875	674043 4945508	850	08/63	1312	6	FR	15	7	12	10	1/00	MU	DUNCOLMN LTD HPAN BLDR 0015 GREY SHLE 0018
RFC	31	64- 5811	674084 4945274	850	05/74	2515	6	FR	18	3	3	5	2/00	DO	HUCALUK FRED BRWN CLAY STNS GRVL 0016 GREY LMSN 0023
RFC	31	64- 7009	674120 4945350	850	05/77	2517	6	FR	22	3	25	3	2/00	DO	SLICHTER JOHN W BRWN TPSL 0001 GREY BLDR CLAY 0018 GREY LMSN 0021 GREY SHLE 0022 GREY LMSN 0028
RFC	31	64- 4709	674120 4945440	875	08/71	1312	6	FR	25	14	25	10	1/00	DO	MACEACHERN S GREY CLAY BLDR 0015 GREY LMSN 0030
RFC	31	64- 2876	674163 4945349	900	08/67	2516	6	FR	27	16	30	3	2/00	DO	WILCOCK J B BLDR 0006 SNDS 0026 LMSN 0040
RFC	31	64- 3543	674200 4945350	900	06/68	2517	6	FR	46	11	44	4	2/00	DO	SIFTON J A GREY CLAY STNS 0020 BLUE CLAY MSND 0045 LMSN 0054
RFC	31	64- 2874	674282 4945543	900	05/62	1312	6	FR	19	4	5	10	1/30	DO	OAKES J R TPSL 0001 CLAY STNS 0019
RFC	32	64- 4121	674160 4945650	848	05/70	2517	6	FR	46	44	50	5	2/00	DO	BARTULZ J CLAY MSND 0015 CLAY 0040 SHLE 0045 LMSN 0052
RFC	32	64- 2879	674174 4945609	850	08/63	1312	6	FR	15	7	12	10	2/00	DO	DUNCOLMN HOLDINGS CLAY HPAN BLDR 0015 GREY LMSN SHLE 0018
RFC	32	64- 2880	674185 4945654	850	07/65	1312	6	FR	16	11	15	7	1/00	DO	DORLAND S M BRWN HPAN BLDR 0016 GREY LMSN SHLE 0019

RFC	32	64- 2878	674207	850 08/62	1312	6 FR	14	4	10	10	7/30 D0	LUOMA E
RFC	32	64- 2877	674218	850 05/62	1312	6 FR	25	10	20	10	1/00 D0	GREY CLAY BLDR 0014 GREY LMSN 0024
RFC	33	64- 4313	674250	850 09/70	2517	6 FR	30	6	6	5	2/00 D0	DUNBRAE HOLDINGS
RFC	34	64- 2881	674740	900 01/58	1344	6 FR	30	15	20	5	1/00 D0	GREY CLAY STNS 0017 GREY LMSN 0027
RFC	35	64- 6954	674770	900 07/76	4512	5 FR	30	40	80	2	1/30 D0	SCOTT RUSSELL
RFC	35	64- 6955	674770	900 07/76	4512	6 FR	98	55	65	20	1/30 D0	GREY CLAY STNS 0024 GREY LMSN 0031
RFC	36	64- 2884	674731	850 01/64	2516	6 FR	115	40	50	12	20/00 CO D0	FARROW H
RFC	36	64- 8778	674900	900 07/81	5415	6	48	15	30	5	24/00 D0	CLAY BLDR 0020 QSN0 0030
RFC	36	64- 2885	674924	900 03/66	2516	FR	40	4	40	4	1/00 D0	TUETS H
RFC	36	64- 5011	674950	900 08/72	3324	6 FR	36	10	59	4	1/00 D0	GREY SHLE LMSN 0006 GREY LMSN 0040 BRWN
RFC	36	64- 2883	674956	900 11/56	5423	6 FR	98	25	25	4	2/00 PS	LMSN 0060 GREY LMSN 0083
RFC	36	64- 5012	675020	900 08/72	5415	6 FR	21	10	15	6	1/00 D0	HUGHES EARL
RFC	36	64- 2882	675476	850 05/50	5423	5 FR	91	20			CO	GREY LMSN 0040 BRWN LMSN 0060 GREY LMSN
RFC	36	64- 2886	675486	900 07/66	2516	6 FR	17	9	52	3	3/00 D0	0098
RFC	37	64- 2888	674226	850 10/50	4223	6 FR	27	9			D0	OLSEN W
RFC	37	64- 2889	674538	850 11/50	4223	5 FR	30	8			D0	SHLE 0003 LMSN 0096 RED GRN1 0115
RFC	37	64- 2892	674542	850 11/60	1312	6 FR	25	8	15	5	1/00 D0	WILMS J
RFC	37	64- 2896	674606	850 02/67	1312	6 FR	34	18	21	25	14/00 D0	GREY LMSN 0048
RFC	37	64- 2891	674611	850 11/60	1312	6 FR	30	10	20	5	1/00 D0	MITCHELL G
RFC	37	64- 2895	674635	850 05/65	1312	6 FR	24	6	35	3	1/00 CO	PRDR 0022 LMSN 0051
RFC	37	64- 2893	674637	850 07/61	5423	6 FR	20	6	15	3	72/00 D0	MITCHELL G
RFC	37	64- 5562	674641	855 01/74	5423	6 FR	29	15	25	10	2/00 D0	GREY LMSN 0059
RFC	37	64- 6948	674650	860 11/76	5415	6 FR	34	10	20	5	2/00 D0	D H O
RFC	37	64- 8100	674650	870 11/79	5415	6 FR	22	5	7	20	2/00 D0	GREY LMSN 0102
RFC	37	64- 2894	674683	850 06/62	1312	6 FR	15	8	9	5	7/30 D0	MITCHELL G
RFC	37	64- 2890	674686	850 05/60	5423	6 FR	40	3	40	5	4/00 D0	GREY LMSN 0021
RFC	37	64- 8777	674700	850 10/81	5415	6 FR	35	10	20	5	2/00 D0	OLSEN W
			4946900									TPSL 0005 LMSN 0091
												BRADDOCK T
												TPSL 0001 LMSN 0052
												ROBERTSON W U
												BLUE CLAY HPAN 0027
												GROZELLE E
												BLUE CLAY STNS 0030
												WILKINSON L
												BRWN CLAY BLDR 0024 SHLE 0025
												WHALEN J
												GREY HPAN BLDR 0018 GREY LMSN 0035
												MCGINNIS G
												BRWN CLAY BLDR 0025 LMSN 0031
												BANK OF COMMERCE
												MSND CLAY HPAN 0008 GREY CLAY HPAN 0015
												GREY SHLE LMSN 0026 GREY LMSN 0042
												WEAVER L
												GREY CLAY BLDR 0020 GRVL 0021
												PEARCE G
												GREY CLAY BLDR 0015 GREY LMSN 0029
												WEAVERS FRANK
												BLCK TPSL 0001 BRWN CLAY 0015 GREY LMSN
												0034
												RUSSELL K
												BLCK TPSL 0001 TPSL 0015 LMSN 0022
												OLSON W
												BRWN CLAY BLDR 0004 GREY CLAY BLDR 0014
												GRVL 0015
												HUMPHRY M
												BLUE CLAY BLDR 0017 LMSN 0040
												NESBITT E
												BLCK TPSL 0001 CLAY BLDR 0010 GREY LMSN
												0035

VICTORIA COUNTY 64

MUNICIPALITY CONCESSION ETC	LOT	WELL NO	UTM EASTING NORTHING	ELEV FEET	DATE	DRILLER	CSG DIA	KIND OF WATER	WATER FOUND FEET	STAT LVL FEET	PUMP LVL FEET	TEST RATE GPM	TEST TIME HR/MN	WATER USE	OWNER/LOG/SCREEN DEPTHS IN FEET TO WHICH FORMATIONS EXTEND
SOMERVILLE TOWNSHIP (CONTINUED....)															
RFC	37	64- 3450	674700 4947170	850	11/68	5415	6	FR	46	15	20	2	2/00	D0	ANGERS PAT TPSL 0001 GREY CLAY BLDR 0030 LMSN 0050
RFC	37	64- 2898	674705 4947132	850	10/67	2516	6	FR	24	4	10	5	3/00	D0	CATON B PRDG 0005 SHLE 0010 LMSN 0024
RFC	37	64- 9030	674750 4947050	900	11/82	5415	6	FR	22	10	15	5	2/00	D0	HENDERSON M BLACK TPSL 0001 CLAY BLDR 0015 LMSN 0022
RFC	37	64- 2887	674764 4947054	850	12/48	5423	5	FR	42	3				CO	BANK OF COMMERCE QSND 0016 LMSN 0042
RFC	37	64- 2897	674788 4947089	850	06/67	5423	6	FR	24	6	16	2	2/00	D0	CATON B GREY SHLE 0010 GREY LMSN 0025
RFC	38	64- 9021	674600 4947400	900	08/82	5415	6	FR	60	20	40	3	2/00	D0	MCALLISTER M BLACK TPSL 0001 CLAY 0010 CLAY BLDR 0033
RFC	38	64- 7450	674700 4947300	850	05/76	1312	6	FR	38	9	28	10	1/00	D0	LMSN 0050 RED GRNT 0060 BOURNS TOM
RFC	38	64- 2906	674702 4947322	850	12/63	1312	6	FR	20	8	10	10	1/00	D0	GREY CLAY HPAN BLDR 0020 GREY LMSN 0039 HALL D
RFC	38	64- 2910	674704 4947237	850	03/65	1312	6	FR	50	26	40	5	1/00	D0	BRWN HPAN 0010 GREY HPAN 0016 GREY LMSN SHLE 0019 GREY LMSN 0026
RFC	38	64- 2908	674710 4947377	850	03/65	2516	6	FR	54	29	32	3	3/00	D0	LAKE S PRDG 0028 GREY CLAY HPAN 0045 SHLE LMSN 0051
RFC	38	64- 4402	674720 4947300	850	05/71	1312	6	FR	50	25	47	10	1/00	D0	CORMIER L PRDG 0026 CLAY STNS GRVL 0040 LMSN 0054 ANGELICAN CHURCH
RFC	38	64- 2903	674757 4947313	850	07/54	2516	5	FR	44	17		2	1/00	D0	BRWN HPAN 0020 GREY HPAN 0042 GREY LMSN 0054
RFC	38	64- 2899	674759 4947243	850	01/49	5423	5	FR	12	6				D0	POVEY D BRWN CLAY STNS 0027 LMSN 0046
RFC	38	64- 2904	674783 4947464	850	05/59	2516	6	FR	44	11	11	5	1/30	D0	RUTTER W QSND BLDR 0036 LMSN 0037
RFC	38	64- 2907	674792 4947336	850	11/64	1312	6	FR	28	14	20	5	2/00	D0	HAXBY G CLAY BLDR 0042 GRVL 0044
RFC	38	64- 5636	674837 4947277	870	04/74	5423	6	FR	52	10	15	5	2/00	D0	BRECHT F G BRWN CLAY HPAN BLDR 0016 GREY LMSN SHLE 0022 GREY LMSN 0028
RFC	38	64- 5480	674870 4947325	870	12/73	1312	6	FR	82	57	86	4	6/00	D0	RUTTER ARN BLACK TPSL 0001 GREY CLAY BLDR 0018 GREY LMSN 0054
RFC	38	64- 2902	674876 4947369	850	11/53	5423	5	FR	66	48		3	72/00	D0	RICHARDSON D BRWN CLAY STNS 0006 GREY LMSN 0092
RFC	38	64- 6406	674900 4937350	900	01/76	5423	6	FR	85	30	30		1/00	D0	WEAVER S GREY LMSN 0045 GRVL 0050 GREY LMSN 0066
RFC	38	64- 2901	674922 4947351	900	11/52	2516	5	FR	90	60		1	1/00	D0	HANDLEY DOUG GREY SHLE 0010 GREY LMSN 0085
RFC	38	64- 5922	674949 4947472	900	12/74	5423	6	FR	90	50	50	1	1/00	D0	FIELDER S E LMSN 0091
RFC	38	64- 2909	674966 4947123	900	02/66	1312	6	FR	80	54	74	5	1/00	D0	MACKAY CLARENCE GREY SHLE LMSN 0010 GREY LMSN 0090
															WEAVER M CLAY 0002 GREY LMSN 0070 BRWN LMSN 0084

6404313

COUNTY OR DISTRICT Victoria	TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE Somerville	CON. BLOCK, TRACT, SURVEY, ETC. 691- Fronting on Riv. R	LOT 033
OWNER (SURNAME FIRST) SCOTT, Russell	ADDRESS Box 151 Bowmanville, Ontario	DATE COMPLETED DAY 02 MO 09	YEAR 70
ZONE V-7	EASTING 674250	NORTHING 4945780	ELEVATION 4 0880 15 24

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

[illegible]

61 002420512 0031215

41 WATER RECORD

WATER FOUND AT - FEET		KIND OF WATER			
0-10	10-15	<input checked="" type="checkbox"/> FRESH	3 <input type="checkbox"/> SULPHUR	14	
2 <input type="checkbox"/> SALTY	4 <input type="checkbox"/> MINERAL				
15-20		1 <input type="checkbox"/> FRESH	3 <input type="checkbox"/> SULPHUR	19	
2 <input type="checkbox"/> SALTY	4 <input type="checkbox"/> MINERAL				
20-25		1 <input type="checkbox"/> FRESH	3 <input type="checkbox"/> SULPHUR	24	
2 <input type="checkbox"/> SALTY	4 <input type="checkbox"/> MINERAL				
25-30		1 <input type="checkbox"/> FRESH	3 <input type="checkbox"/> SULPHUR	29	
2 <input type="checkbox"/> SALTY	4 <input type="checkbox"/> MINERAL				
30-35		1 <input type="checkbox"/> FRESH	3 <input type="checkbox"/> SULPHUR	34	
2 <input type="checkbox"/> SALTY	4 <input type="checkbox"/> MINERAL				

51 CASING & OPEN HOLE RECORD

INSIDE DIAM INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET	
			FROM	TO
6 1/2 06	<input checked="" type="checkbox"/> STEEL <input checked="" type="checkbox"/> GALVANIZED <input type="checkbox"/> CONCRETE <input type="checkbox"/> OPEN HOLE	.188	0	31 (0031)
1 1/8	<input type="checkbox"/> STEEL <input type="checkbox"/> GALVANIZED <input type="checkbox"/> CONCRETE <input type="checkbox"/> OPEN HOLE			
2 1/4	<input type="checkbox"/> STEEL <input type="checkbox"/> GALVANIZED <input type="checkbox"/> CONCRETE <input type="checkbox"/> OPEN HOLE			

Z	SIZE(S) OF OPENING	20-31	DIAMETER	28-38	LENGTH	28-40
	(SLOT NO.)					

SCREEN		INCHES	FEET
	MATERIAL AND TYPE	DEPTH TO TOP OF SCREEN	41-44
		FEET	80

61 PLUGGING & SEALING RECORD

DEPTH SET AT - FEET		MATERIAL AND TYPE (CEMENT GROUT, LEAD PACKER, ETC.)
FROM	TO	
10.1	14.1	
18.1	22.5	
29.1	30.3	

PUMPING TEST

PUMPING TEST METHOD		PUMPING RATE		DURATION OF PUMPING	
<input type="checkbox"/> PUMP <input checked="" type="checkbox"/> BAILER		1705 GPM		02 HOURS 10 MINS	
STATIC LEVEL		WATER LEVEL END OF PUMPING		<input checked="" type="checkbox"/> PUMPING <input type="checkbox"/> RECOVERY	
		WATER LEVELS DURING			
		15 MINUTES		30 MINUTES	
		45 MINUTES		60 MINUTES	
006 FEET		006 FEET		006 FEET	
006 FEET		006 FEET		006 FEET	
IF FLOWING, GIVE RATE		PUMP INTAKE SET AT		WATER AT END OF TEST	
GPM		30 FEET		<input checked="" type="checkbox"/> CLEAR <input type="checkbox"/> CLOUDY	
RECOMMENDED PUMP TYPE		RECOMMENDED PUMP SETTING		RECOMMENDED PUMPING RATE	
<input checked="" type="checkbox"/> SHALLOW <input type="checkbox"/> DEEP		C130 FEET		26.43 GPM	
10-55		016.0 GPM/FT. SPECIFIC CAPACITY		006.5 GPM	

LOCATION OF WELL

[illegible]

WELL NO.	DATE	FINAL STATUS OF WELL
1	1/1/70	ABANDONED
2	1/1/70	ABANDONED
3	1/1/70	ABANDONED
4	1/1/70	ABANDONED
5	1/1/70	ABANDONED
6	1/1/70	ABANDONED
7	1/1/70	ABANDONED
8	1/1/70	ABANDONED
9	1/1/70	ABANDONED
10	1/1/70	ABANDONED
11	1/1/70	ABANDONED
12	1/1/70	ABANDONED
13	1/1/70	ABANDONED
14	1/1/70	ABANDONED
15	1/1/70	ABANDONED
16	1/1/70	ABANDONED
17	1/1/70	ABANDONED
18	1/1/70	ABANDONED
19	1/1/70	ABANDONED
20	1/1/70	ABANDONED
21	1/1/70	ABANDONED
22	1/1/70	ABANDONED
23	1/1/70	ABANDONED
24	1/1/70	ABANDONED
25	1/1/70	ABANDONED
26	1/1/70	ABANDONED
27	1/1/70	ABANDONED
28	1/1/70	ABANDONED
29	1/1/70	ABANDONED
30	1/1/70	ABANDONED
31	1/1/70	ABANDONED
32	1/1/70	ABANDONED
33	1/1/70	ABANDONED
34	1/1/70	ABANDONED
35	1/1/70	ABANDONED
36	1/1/70	ABANDONED
37	1/1/70	ABANDONED
38	1/1/70	ABANDONED
39	1/1/70	ABANDONED
40	1/1/70	ABANDONED
41	1/1/70	ABANDONED
42	1/1/70	ABANDONED
43	1/1/70	ABANDONED
44	1/1/70	ABANDONED
45	1/1/70	ABANDONED
46	1/1/70	ABANDONED
47	1/1/70	ABANDONED
48	1/1/70	ABANDONED
49	1/1/70	ABANDONED
50	1/1/70	ABANDONED
51	1/1/70	ABANDONED
52	1/1/70	ABANDONED
53	1/1/70	ABANDONED
54	1/1/70	ABANDONED
55	1/1/70	ABANDONED
56	1/1/70	ABANDONED
57	1/1/70	ABANDONED
58	1/1/70	ABANDONED
59	1/1/70	ABANDONED
60	1/1/70	ABANDONED
61	1/1/70	ABANDONED
62	1/1/70	ABANDONED
63	1/1/70	ABANDONED
64	1/1/70	ABANDONED
65	1/1/70	ABANDONED
66	1/1/70	ABANDONED
67	1/1/70	ABANDONED
68	1/1/70	ABANDONED
69	1/1/70	ABANDONED
70	1/1/70	ABANDONED
71	1/1/70	ABANDONED
72	1/1/70	ABANDONED
73	1/1/70	ABANDONED
74	1/1/70	ABANDONED
75	1/1/70	ABANDONED
76	1/1/70	ABANDONED
77	1/1/70	ABANDONED
78	1/1/70	ABANDONED
79	1/1/70	ABANDONED
80	1/1/70	ABANDONED
81	1/1/70	ABANDONED
82	1/1/70	ABANDONED
83	1/1/70	ABANDONED
84	1/1/70	ABANDONED
85	1/1/70	ABANDONED
86	1/1/70	ABANDONED
87	1/1/70	ABANDONED
88	1/1/70	ABANDONED
89	1/1/70	ABANDONED
90	1/1/70	ABANDONED
91	1/1/70	ABANDONED
92	1/1/70	ABANDONED
93	1/1/70	ABANDONED
94	1/1/70	ABANDONED
95	1/1/70	ABANDONED
96	1/1/70	ABANDONED
97	1/1/70	ABANDONED
98	1/1/70	ABANDONED
99	1/1/70	ABANDONED
100	1/1/70	ABANDONED

WATER USE <i>01</i>	<input checked="" type="checkbox"/> DOMESTIC	<input type="checkbox"/> COMMERCIAL
	<input type="checkbox"/> STOCK	<input type="checkbox"/> MUNICIPAL
	<input type="checkbox"/> IRRIGATION	<input type="checkbox"/> PUBLIC SUPPLY
	<input type="checkbox"/> INDUSTRIAL	<input type="checkbox"/> COOLING OR AIR CONDITIONING
	<input type="checkbox"/> OTHER	<input type="checkbox"/> NOT USED
METHOD OF DRILLING	<input checked="" type="checkbox"/> CABLE TOOL	<input type="checkbox"/> BORING
	<input type="checkbox"/> ROTARY (CONVENTIONAL)	<input type="checkbox"/> DIAMOND
	<input type="checkbox"/> ROTARY (REVERSE)	<input type="checkbox"/> JETTING
	<input type="checkbox"/> ROTARY (AIR)	<input type="checkbox"/> DRIVING
	<input type="checkbox"/> AIR PERCUSSION	

TRACTOR

NAME OF WELL CONTRACTOR	G. HART AND SONS	LICENCE NUMBER
Kenneth H. Hart		2517
ADDRESS		
R.R.1, Fenelon Falls, Ontario		

USE ONLY

DATA SOURCE	1	SP CONTRACTOR	2517	DATE	12/21/12	01-00	60
DATE OF USE	12/21/12	INSPECTOR					

44 2881

#64 2881

Pipe and Casing Record

Pumping Test

Casing diameter (s)	5.28	Static level	15 ft
Length (s)	30'	Pumping rate	300 gals/min
Type of screen	NONE	Pumping level	20 ft
Length of screen		Duration of test	1 hr

Static level 1.5 ft
Pumping rate 300 g/min
Pumping level 20 ft
Duration of test 1 hr

Well Log

Water Record

[illegible]

For what purpose(s) is the water to be used?

Arminio Kienle

Is water clear or cloudy? *cloudy*

Is well on upland, in valley, or on hillside?.....

Drilling firm Wm. H. F. Adams

Address Begun, O.T.

Name of Driller Ed. J. B. ...

Address 1000 1st St. N. W.

Licence Number. 11 57


I certify that the foregoing
statements of fact are true.

Date Nov 9/48 Dept. of Health

Signature of Licensee _____

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.



1. PRINT ONLY IN SPACES PROVIDED

2. CHECK ☒ CORRECT BOX WHERE APPLICABLE

64012 RFS

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

USE ONLY	DATA	56	CONTRACTOR	59-62	DATE RECEIVED	63-66	90
	SOURCE		4512		1050477		
	DATE OF INSPECTION		INSPECTOR				



The Ontario Water Resources Commission Act

WATER WELL RECORD

GROUND WATER BRANCH 2884
64
MAY 25 1964
ONTARIO WATER SOURCES COMMISSION

Basin
County or District

Com.

Lot

Township, Village, Town or City

Date completed

(day)

month

year

Owner

Address

Casing and Screen Record**Pumping Test**

Inside diameter of casing

Total length of casing

Type of screen

Length of screen

Depth to top of screen

Diameter of finished hole

Static level

Test-pumping rate

G.P.M.

Pumping level

Duration of test pumping

Water clear or cloudy at end of test

Recommended pumping rate

G.P.M.

with pump setting of

feet below ground surface

Well Log**Water Record****Overburden and Bedrock Record**From
ft.To
ft.Depth(s) at
which water(s)
foundKind of water
(fresh, salty,
sulphur)

SHALE ROCK

0

3

LIMESTONE ROCK

3'

96'

RED GRANITE

96'

115'

115'

FRESH

For what purpose(s) is the water to be used?

HOUSE & GARAGE

Is well on upland, in valley, or on hillside?

UPLAND

Drilling or Boring Firm

C. HART: SON

Address

R. R. #1

FENELON FALLS

Licence Number

818

Name of Driller or Borer

DON HART

Address

SAME AS ABOVE

Date

JAN 14 1964

Don Hart


(Signature of Licensed Drilling or Boring Contractor)

Form 1531-60-4138

OWRC COPY

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.





64 No 2886

The Ontario Water Resources Commission Act

WATER WELL RECORD

Basin 24

County or District

VICTORIA

Township, Village, Town or City SOMERVILLE

Con. F. RANGE

Lot 36

Date completed 14 JULY 1966

Owner MR. TIM BRADDOCK

(print in block letters)

Address R. R. #. I. FENELON FALLS

Casing and Screen Record

Pumping Test

Inside diameter of casing 6 1/4"
Total length of casing 9'
Type of screen
Length of screen
Depth to top of screen
Diameter of finished hole 6 1/4"

Static level 9'
Test-pumping rate 3 G.P.M.
Pumping level empty
Duration of test pumping 3 hrs.
Water clear or cloudy at end of test clear
Recommended pumping rate 2 G.P.M.
with pump setting of 50' feet below ground surface

Well Log

Water Record

Overburden and Bedrock Record	From ft.	To ft.	Depth(s) at which water(s) found	Kind of water (fresh, salty, sulphur)
TOP SOIL	0	1	17	FRESH
LIMESTONE ROCK	1	52		

For what purpose(s) is the water to be used?

HOUSE

UPLAND

Is well on upland, in valley, or on hillside?

Drilling or Boring Firm

G. HART & SONS

Address

R. R. #. I. FENELON FALLS

Licence Number

2242

Name of Driller or Borer

DONALD HART

Address R. R. #. 3. FENELON FALLS


Date JULY 14, 1966

(Signature of Licensed Drilling or Boring Contractor)

Form 7 15M-60-4138

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.



O.W.R.C. COPY



FRONT RANGE

The Ontario Water Resources Commission Act

WATER RESOURCES DIVISION

Map R 30.90.0

WATER WELL RECORD

MAY 31 1968

County or District *Victoria*

Township, Village, Town or City *Simcoe*

Con. *7*

Lot *36*

Date completed *25* *March* *1966*

Owner *Gilbert Mitchell*
(print in block letters)

Address *P.O. Box 1, Cobourg, Ont.*

Casing and Screen Record

Pumping Test

Inside diameter of casing *5 5/8*
Total length of casing
Type of screen
Length of screen
Depth to top of screen
Diameter of finished hole *5 inches*

Static level *4 ft*
Test-pumping rate
Pumping level *40 ft*
Duration of test pumping *1 hr*
Water clear or cloudy at end of test *Clear*
Recommended pumping rate *4* G.P.M.
with pump setting of *50* feet below ground surface

Well Log


Water Record

From	To	Depth(s) at which water(s) found	Kind of water (fresh, salty, sulphur)
<i>22</i>	<i>51</i>	<i>40'</i>	<i>fresh</i>

For what purpose(s) is the water to be used? *house*
Is well on upland, in valley, or on hillside? *upland*
Drilling or Boring Firm *George Hart & Sons*
Address *R.R. # 3, Fenelon Falls, Ont.*
Licence Number *1965*
Name of Driller or Borer *GEORGE HART*
Address *same as above*
Date *March 25/66*
G. Hart
(Signature of Licensed Drilling or Boring Contractor)
(Per m. H.)

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.



Form 7 15M-60-4138

OWRC COPY

2. CHECK ☒ CORRECT BOX WHERE APPLICABLE

John R. C. T. H. H.

POINT	COMS	EASTING	NORTHING	DE	ELEVATION	BASE FORM
21	1.7	167495.0	149466.520	4	0.900	2.4

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

[illegible]

0059215

41 WATER RECORD

WATER FOUND AT - FEET		KIND OF WATER			
0-36	1	<input checked="" type="checkbox"/> FRESH	3	<input type="checkbox"/> SULPHUR	
	2	<input type="checkbox"/> SALTY	4	<input type="checkbox"/> MINERAL	
10-18	1	<input type="checkbox"/> FRESH	3	<input type="checkbox"/> SULPHUR	
	2	<input type="checkbox"/> SALTY	4	<input type="checkbox"/> MINERAL	
20-23	1	<input type="checkbox"/> FRESH	3	<input type="checkbox"/> SULPHUR	
	2	<input type="checkbox"/> SALTY	4	<input type="checkbox"/> MINERAL	
10-26	1	<input type="checkbox"/> FRESH	3	<input type="checkbox"/> SULPHUR	
	2	<input type="checkbox"/> SALTY	4	<input type="checkbox"/> MINERAL	
30-41	1	<input type="checkbox"/> FRESH	3	<input type="checkbox"/> SULPHUR	
	2	<input type="checkbox"/> SALTY	4	<input type="checkbox"/> MINERAL	

CASING & OPEN HOLE RECORD

INSIDE DIA. INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET	
			FROM	TO
06 164	<input checked="" type="checkbox"/> STEEL <input type="checkbox"/> GALVANIZED <input type="checkbox"/> CONCRETE <input type="checkbox"/> OPEN HOLE	188	0	6 0006
17-18 06 174	<input type="checkbox"/> STEEL <input type="checkbox"/> GALVANIZED <input type="checkbox"/> CONCRETE <input checked="" type="checkbox"/> OPEN HOLE	1	6	0035 59
14-25 30	<input type="checkbox"/> STEEL <input type="checkbox"/> GALVANIZED <input type="checkbox"/> CONCRETE <input type="checkbox"/> OPEN HOLE			

SCREEN	SIZE OF OPENING (SLOT NO.)	31-33	DIA-STEM	34-38	LENGTH	39-40
				INCHES		FEET
	MATERIAL AND TYPE	DEPTH TO TOP OF SCREEN		41-42	43	44
				FEET		

61 PLUGGING & SEALING RECORD


DEPTH SET AT - FEET		MATERIAL AND TYPE	(CEMENT GROUT, LEAD PACKER, ETC.)
FROM	TO		
30-13	31-17		
18-21	22-25		
26-28	30-33		

10	PUMPING TEST METHOD	10	PUMPING TEST METHOD	M-14	PUMPING TEST METHOD
----	---------------------	----	---------------------	------	---------------------

PUMPING TEST	<input type="checkbox"/> PUMP <input checked="" type="checkbox"/> SAILER		DURATION OF PUMPING 01 HOURS 00 MIN		
	STATIC LEVEL 10 21 010		WATER LEVEL END OF PUMPING 15 24 059		
	WATER LEVELS DURING 15 24 025		<input type="checkbox"/> PUMPING <input checked="" type="checkbox"/> RECOVERY		
	30 MINUTES 010		45 MINUTES 010		
	60 MINUTES 010		75 MINUTES 010		
IF FLOWING GIVE RATE		PUMP INTAKE SET AT		WATER AT END OF TEST	
RECOMMENDED PUMP TYPE <input type="checkbox"/> SHALLOW <input checked="" type="checkbox"/> DEEP		RECOMMENDED PUMP SAILER		RECOMMENDED PUMPING RATE 000.1	
00-13		000.1		000.1	

LOCATION OF WELL

IN DIAGRAM BELOW SHOW DISTANCES OF WELL FROM ROAD AND LOT LINE. INDICATE NORTH BY ARROW.



FINAL ☒ WATER SUPPLY ☐ ABANDONED INSUFFICIENT SUPPLY

STATUS OF WELL	<input type="checkbox"/> OBSERVATION WELL <input type="checkbox"/> TEST HOLE <input type="checkbox"/> RECHARGE WELL	<input type="checkbox"/> ABANDONED POOR QUALITY <input type="checkbox"/> EXHAUSTED
WATER USE	1 <input checked="" type="checkbox"/> DOMESTIC 2 <input type="checkbox"/> STOCK 3 <input type="checkbox"/> IRRIGATION 4 <input type="checkbox"/> INDUSTRIAL 5 <input type="checkbox"/> OTHER	6 <input type="checkbox"/> COMMERCIAL 7 <input type="checkbox"/> MUNICIPAL 8 <input type="checkbox"/> PUBLIC SUPPLY 9 <input type="checkbox"/> COOLING OR AIR CONDITIONING 10 <input type="checkbox"/> NOT USED
METHOD OF DRILLING	1 <input type="checkbox"/> CABLE TOOL 2 <input type="checkbox"/> ROTARY - CONVENTIONAL 3 <input type="checkbox"/> ROTARY - RESERVE 4 <input type="checkbox"/> ROTARY - AIR 5 <input type="checkbox"/> AIR PERCUSSION	6 <input type="checkbox"/> BORING 7 <input type="checkbox"/> DIAMOND 8 <input type="checkbox"/> JETTING 9 <input type="checkbox"/> DRIPPING

NAME OF WELL CONTRACTOR	C. WEAVER	WELL NUMBER	3324

COPIES OF THIS REPORT ARE BEING FURNISHED TO THE FOLLOWING:

1. 3324 121272

DATE OF INSPECTION: 5/11/33

INSPECTOR: T. J.

WATER WELL RECONNAISSANCE SURVEY Sheet ___ of ___

Sheet ___ of ___

PROJECT NAME Coboconk PROJECT NO 88-237
PERSON INTERVIEWED Gene Suggitt RESIDENCE Texaco
DATE August 24/88 TIME 9:50 INTERVIEWED BY PW

OWNER OF WELL:

Name:.....Jim Hannivan.....Telephone (Bus.)...454-3962..

Address: Box 84, Cabaconk.....(incl. Area Code) (Home).....454-3346

OCCUPANT OF HOUSE SERVED BY WELL (if other than owner):

Name:.....Mrs. Hannivan (owner's mother).....Telephone (Bus.).....

Address:.....Directly Beside (north) of.....(incl. Area Code) (Home).....
 Texaco Station

WELL LOCATION: Lot.....Concession.....Township.....

WELL CONSTRUCTION DETAILS:

Date constructed.....Use.....Contractor.....

Type (drilled or dug).....Diameter.....Well Depth.....

Is well accessible for direct sampling.....or buried.....

Well completed into Bedrock.....m. Overburden.....m

Screen: Yes.... No.... If yes, length.....m. Depth to top of screen.....m

WELL WATER LEVELS:

(Indicate whether measured from ground level, or from top of casing)

Original water level depth.....m.

Subsequent water level measurements (give depths in m and dates).....

PUMPING EQUIPMENT:

Pump Type: Suction-lift....or Positive-submergence....Pumping capacity.....Age...

How is your pump lubricated?.....

Depth of intake setting.....m (Original).....m (present) Pumping rate....L/s

Storage tank: Type..... Capacity.....

Do you have a:

Chlorinator.....Water Softener.....Water Filter.....Filter Type.....

Water use: Domestic No...Yes... No. of persons using water from well

Livestock No...Yes... No. of livestock watered from well

Lawn watering No...Yes... Other..... Amount.....

Equipment: Indoor plumbing (e.g. shower, automatic washer, etc.).....

Private waste and water disposal: Type (septic tank, etc.).....

Distance to well

Well is (1) Uphill..... (2) Downhill..... (3) Same Grade

(continued on reverse..)

WATER WELL RECONNAISSANCE SURVEY Sheet ____ of ____

(continued on reverse..)

WATER WELL RECONNAISSANCE SURVEY Sheet ____ of ____

PROJECT NAME Coboconk PROJECT NO 88-237
PERSON INTERVIEWED Mary Spry/Mrs. Mitchell RESIDENCE X
DATE August 24/88 TIME 12:20 INTERVIEWED BY PW

OWNER OF WELL:

Name:.....Mrs. Mitchell.....Telephone (Bus.).....

Address:.....(incl. Area Code) (Home).....

OCCUPANT OF HOUSE SERVED BY WELL (if other than owner):

Name: Mrs. Mitchell Telephone (Bus.)

Address:.....(incl. Area Code) (Home).....

WELL LOCATION: Lot.....Part 35.....Concession.....Front
Range.....Township.....

WELL CONSTRUCTION DETAILS:

Date constructed May 17/88 Use X Contractor Weaver

Type (drilled or dug) drilled Diameter 6 1/4 in. Well Depth 92 ft

Is well accessible for direct sampling.....or buried.....

Well completed into Bedrock.....Yes.....m. Overburden 1-4 ft. of clay....m

Screen: Yes.... No.... If yes, length.....m. Depth to top of screen.....m

WELL WATER LEVELS:

(Indicate whether measured from ground level, or from top of casing) Pumping rate: 20 GPM

Original water level depth.....90 ft.....m. Duration of pumping: 1 hr

Subsequent water level measurements (give depths in m and dates).....

Water level end of pumping: 60 ft

Pump intake set at 85 ft

PUMPING EQUIPMENT:

Pump Type: Suction-lift....or Positive-submergence....Pumping capacity.....Age... construction

How is your pump lubricated?.....

Depth of intake setting.....m (Original).....m (present) Pumping rate....L/s

Storage tank: Type..... Capacity.....

Do you have a:

Chlorinator..No...Water Softener..No....Water Filter..No.....Filter Type.....

Water use: Domestic No...Yes.X. No. of persons using water from well1.....

Livestock No. ^X Yes... No. of livestock watered from well

Lawn watering No...Yes^X... Other..... Amount.....

Equipment: Indoor plumbing (e.g. shower, automatic washer, etc.)...shower, washer.

Private waste and water disposal: Type (septic tank, etc.) Septic.....

Distance to well45 ft.

Well is (1) Uphill..... (2) Downhill slightly (3) Same Grade

(continued on reverse..)

WATER WELL RECONNAISSANCE SURVEY Sheet ____ of ____

PROJECT NAME Coboconk PROJECT NO 88-237
PERSON INTERVIEWED Colleen Liscombe RESIDENCE Store
DATE August 24/88 TIME 10:20 INTERVIEWED BY PW

OWNER OF WELL:

Name:..... Pam Wilcox.....Telephone (Bus.).....454-1401
Address:..... The Millworks Store.....(incl. Area Code) (Home).....454-8879

OCCUPANT OF HOUSE SERVED BY WELL (if other than owner):

Name:.....Telephone (Bus.).....
Address:.....(incl. Area Code) (Home).....

WELL LOCATION: Lot.....Concession.....Township.....

WELL CONSTRUCTION DETAILS:

Date constructed.....Use.....Contractor.....
Type (drilled or dug).....Diameter.....Well Depth.....
Is well accessible for direct sampling.....or buried.....
Well completed into Bedrock.....m. Overburden.....m
Screen: Yes.... No.... If yes, length.....m. Depth to top of screen.....m

WELL WATER LEVELS:

(Indicate whether measured from ground level, or from top of casing)

Original water level depth.....m.

Subsequent water level measurements (give depths in m and dates).....

.....

PUMPING EQUIPMENT:

Pump Type: Suction-lift....or Positive-submergence....Pumping capacity.....Age...
How is your pump lubricated?.....
Depth of intake setting.....m (Original).....m (present) Pumping rate....L/s
Storage tank: Type..... Capacity.....
Do you have a:
Chlorinator.....Water Softener.....Water Filter.....Filter Type.....
Water use: Domestic No...Yes... No. of persons using water from well
Livestock No...Yes... No. of livestock watered from well
Lawn watering No...Yes... Other..... Amount.....
Equipment: Indoor plumbing (e.g. shower, automatic washer, etc.).....
.....
Private waste and water disposal: Type (septic tank, etc.).....
Distance to well
Well is (1) Uphill..... (2) Downhill..... (3) Same Grade

(continued on reverse..)

WATER WELL RECONNAISSANCE SURVEY Sheet ____ of ____

Sheet ___ of ___

PROJECT NAME Coboconk PROJECT NO 88-237
PERSON INTERVIEWED Leslie Frances RESIDENCE X
DATE August 24/88 TIME 10:40 INTERVIEWED BY PW

OWNER OF WELL:

Name:.....Leslie Frances.....Telephone (Bus.).....

Address:.....(incl. Area Code) (Home) 454-1262.

OCCUPANT OF HOUSE SERVED BY WELL (if other than owner):

Name:..Leslie Frances.....Telephone (Bus.).....

Address:.....(incl. Area Code) (Home).....

WELL LOCATION: Lot.....Part Lot 36.....Concession.....7.....Township.....

WELL CONSTRUCTION DETAILS:

Date constructed.....Use.....Contractor.....

Type (drilled or dug).....Diameter.....Well Depth.....

Is well accessible for direct sampling.....or buried.....

Well completed into Bedrock.....m. Overburden.....m.

Screen: Yes.... No.... If yes, length.....m. Depth to top of screen.....m

WELL WATER LEVELS:

(Indicate whether measured from ground level, or from top of casing)

Original water level depth.....m.

Subsequent water level measurements (give depths in m and dates).....

PUMPING EQUIPMENT:

Pump Type: Suction-lift....or Positive-submergence....Pumping capacity.....Age...

How is your pump lubricated?.....

Depth of intake setting.....m (Original).....m (present) Pumping rate....L/s

Storage tank: Type..... Capacity.....

Do you have a:

Chlorinator.....Water Softener.....Water Filter.....Filter Type.....

Water use: Domestic No...Yes...^X No. of persons using water from well¹.....

Livestock No. ^X Yes... No. of livestock watered from well

Lawn watering No. ^X Yes... Other..... Amount.....

Equipment: Indoor plumbing (e.g. shower, automatic washer, etc.)..shower.....

Private waste and water disposal: Type (septic tank, etc.)...Septic.....

Distance to well 37 ft

Well is (1) Uphill..... (2) Downhill..... (3) Same Grade^X

(continued on reverse..)

WATER WELL RECONNAISSANCE SURVEY Sheet ____ of ____

PROJECT NAME Coboconk PROJECT NO 88-237
PERSON INTERVIEWED Gayle Webster RESIDENCE X
DATE August 24/88 TIME 1:30 INTERVIEWED BY PW

OWNER OF WELL:

Name: Earl Hughes Telephone (Bus.)

Address:.....(incl. Area Code) (Home). (705). 454-3944

OCCUPANT OF HOUSE SERVED BY WELL (if other than owner):

Name: Earl Hughes Telephone (Bus.)

Address:.....(incl. Area Code) (Home).....

WELL LOCATION: Lot.....Concession.....Township.....

WELL CONSTRUCTION DETAILS:

ELL CONSTRUCTION DETAILS: Lenridge Well
Date constructed 14 years Use Contractor Drilling

Type (drilled or dug).....drilled.....Diameter.....Well Depth...100 ft

Is well accessible for direct sampling.....concrete cover or buried.....

Well completed into Bedrock...^{Yes}.....m. Overburden.....m

Screen: Yes.... No.... If yes, length.....m. Depth to top of screen.....m

WELL WATER LEVELS:

(Indicate whether measured from ground level, or from top of casing)

Original water level depth.....m.

Subsequent water level measurements (give depths in m and dates).....

PUMPING EQUIPMENT:

Pump Type: Suction-lift...or Positive-submergence...X...Pumping capacity.....Age...

How is your pump lubricated?.....

Depth of intake setting.....m (Original).....m (present) Pumping rate....L/s

Storage tank: Type..... Capacity.....

Do you have a:

Chlorinator.....No.....Water Softener.....X.....Water Filter.....X.....Filter Type.....

Water use: Domestic No...Yes..^X No. of persons using water from well2.....

Livestock No. ^X Yes... No. of livestock watered from well

Lawn watering No...Yes...^X Other..... Amount.....

Equipment: Indoor plumbing (e.g. shower, automatic washer, etc.).....

Private waste and water disposal: Type (septic tank, etc.)....Septic.....

Distance to well 45 ft

Well is (1) Uphill..... (2) Downhill..... (3) Same Grade^X.....

(continued on reverse..)

WATER WELL RECONNAISSANCE SURVEY Sheet ____ of ____

PROJECT NAME	Coboconk	PROJECT NO	88-237
PERSON INTERVIEWED	Wilma Baker	RESIDENCE	X
DATE	August 24/88	TIME	11:10
		INTERVIEWED BY	PW

OWNER OF WELL:

Name: Ray & Wilma Baker Telephone (Bus.)
Address: (incl. Area Code) (Home) 454-1263

OCCUPANT OF HOUSE SERVED BY WELL (if other than owner):

Name: Ray & Wilma Baker Telephone (Bus.)
Address: (incl. Area Code) (Home)

WELL LOCATION: Lot...Part 36.....Concession.....7.....Township.....

WELL CONSTRUCTION DETAILS:

```

Date constructed.....14 years.....Use.....Contractor.....Gordy Weaver.....
Type (drilled or dug).....drilled.....Diameter.....Well Depth.....57 ft
Is well accessible for direct sampling.....concrete covered.....or buried.....
Well completed into Bedrock.....Yes.....m.....Overburden.....m
Screen: Yes.... No.... If yes, length.....m.....Depth to top of screen.....m

```

WELL WATER LEVELS:

(Indicate whether measured from ground level, or from top of casing)

Original water level depth.....m.

Subsequent water level measurements (give depths in m and dates).....

PUMPING EQUIPMENT:

Pump Type: Suction-lift....or Positive-submergence....Pumping capacity.....Age.2 months

How is your pump lubricated?.....

Depth of intake setting.....m (Original).....m (present) Pumping rate....L/s

Storage tank: Type..... Capacity.....

Do you have a: Clear 'n' Fresh
Envirogard Products
Chlorinator.....No.....Water Softener.....No.....Water Filter.....X.....Filter Type.....Ltd.....

Water use: Domestic No...Yes...^X No. of persons using water from well ...³.....
 Livestock No...Yes...^X No. of livestock watered from well
 Lawn watering No...Yes...^X Other..... Amount.....

Equipment: Indoor plumbing (e.g. shower, automatic washer, etc.) shower.....

Private waste and water disposal: Type (septic tank, etc.).....Septic.....

Distance to well 52 ft.

Well is (1) Uphill..... (2) ~~Downhill~~..... (3) Same Grade^X

(continued on reverse..)

WATER WELL RECONNAISSANCE SURVEY Sheet ____ of ____

PROJECT NAME Coboconk PROJECT NO 88-237
PERSON INTERVIEWED John Wilms RESIDENCE X
DATE August 24/88 TIME 11:30 INTERVIEWED BY PW

OWNER OF WELL:

Name: John Wilms Telephone (Bus.)

Address:.....(incl. Area Code) (Home) 454-8112.

OCCUPANT OF HOUSE SERVED BY WELL (If other than owner):

Name: John Wilms Telephone (Bus.)

Address:.....(incl. Area Code) (Home).....

WELL LOCATION: Lot.....Part 36.....Concession.....7.....Township.....

WELL CONSTRUCTION DETAILS:

Date constructed 8 years Use ☒ Contractor Gordy Weaver

Type (drilled or dug).....drilled.....Diameter..6-8 inch..Well Depth..48.ft

Is well accessible for direct sampling.....^{No}.....or buried.....

Well completed into Bedrock.....^{Yes}.....m. Overburden.....m

Screen: Yes.... No.... If yes, length.....m. Depth to top of screen.....m

WELL WATER LEVELS:

(Indicate whether measured from ground level, or from top of casing)

Original water level depth...15 ft. from ground...m.
surface when drilled

Subsequent water level measurements (give depths in m and dates).....No.....

PUMPING EQUIPMENT:

Pump Type: Suction-lift....or Positive-submergence....Pumping capacity.....Age⁸ years

How is your pump lubricated?.....sealed bearings.....

Depth of intake setting.....m (Original).....m (present) Pumping rate....L/s

Storage tank: Type.....No..... Capacity.....

Do you have a:

Chlorinator.....No.....Water Softener.....No.....Water Filter.....No.....Filter Type.....

Water use: Domestic No...Yes^X... No. of persons using water from well⁵.....

Livestock No...Yes^X.. No. of livestock watered from well1.....

Lawn watering No. ^X Yes... Other..... Amount.....

Equipment: Indoor plumbing (e.g. shower, automatic washer, etc.)..washer..bathtub-
no shower, dishwasher

Private waste and water disposal: Type (septic tank, etc.)...Septic.....

Distance to well 44 ft


Well is (1) Uphill..... (2) Downhill..... (3) Same GradeX

(continued on reverse..)

APPENDIX III




- **BOREHOLE LOGS**
- **HAND AUGER BOREHOLE LOGS**
- **MONITOR DETAILS SUMMARY**
- **SLUG TEST ANALYSIS PLOTS**

BOREHOLE LOG		PROJECT NO. <u>88-237</u>	BOREHOLE NO. <u>1</u>
PROJECT NAME <u>Coboconk Waste Disposal Site</u>		DATE <u>17 August 1988</u>	
<u>Coboconk, Ontario</u>		GEOLOGIST <u>PW</u>	
CLIENT <u>Ministry of the Environment</u>		ELEVATION <u>280.79 masl</u>	

DEPTH (m)	STRATIGRAPHY	STRATIGRAPHIC DESCRIPTION	MONITOR DETAILS & NUMBER		SAMPLE						Penetration Resistance N VALUE (Blows/0.3m)				Water Content (%) w _c <input type="checkbox"/>		
			I	II	INTERVAL	NO.	TYPE	N VALUE	%RECOVERY	%WATER	%RQD						
												10	20	30	40	10	20
1		LIMESTONE (Gull River Formation) Grey-Brown, fractured with sand, shale and clay seams				1	NQ	80		4							
2.1		Grey, fractured with clay seams and horizontal shaley partings, some vertical fractures with well developed crystals on fracture faces, fine to medium grained, laminated, fossiliferous															
3						2	NQ	90		0							
4						3	NQ	90		0							
5						4	NQ	100		53							
6						5	NQ	100		48							
7						6	NQ	100		60							
8						7	NQ	100		86							
9																	
10																	
10.7		NQ corehole terminated at 10.7 m in fractured limestone.															

P-Piezometer S-Standpipe G-Gas Monitor

BOREHOLE LOG	PROJECT NO. <u>88-237</u>	BOREHOLE NO. <u>2</u>
PROJECT NAME <u>Coboconk Waste Disposal Site</u>		DATE <u>18 August 1988</u>
<u>Coboconk, Ontario</u>		GEOLOGIST <u>PW</u>
CLIENT <u>Ministry of the Environment</u>		ELEVATION <u>276.98 masl</u>

DEPTH (m)	STRATIGRAPHY	STRATIGRAPHIC DESCRIPTION	MONITOR DETAILS & NUMBER		SAMPLE						Penetration Resistance N VALUE (Blows/0.3m)				Water Content (%) w _c <input type="checkbox"/>				
			I	II	INTERVAL	NO.	TYPE	N VALUE	%RECOVERY	%WATER	%RQD								
												10	20	30	40	10	20	30	
1		LIMESTONE (Gull River Formation) Grey, fractured with shaley parting and vuggy sections, fine to medium grained, laminated, fossiliferous			1	NQ		100		19									
					2	NQ		100		31									
2						3	NQ		100		56								
3								4	NQ		100		75						
4																			
5								5	NQ		100		80						
6																			
					6	NQ		100		88									
7																			
8																			
					7	NQ		100		79									
9.1																			
9		NQ Corehole terminated at 9.1 m in fractured limestone.																	

P-Piezometer S-Standpipe G-Gas Monitor

BOREHOLE LOG		PROJECT NO. <u>88-237</u>	BOREHOLE NO. <u>3</u>
PROJECT NAME <u>Coboconk Waste Disposal Site</u>		DATE <u>18 August 1988</u>	
<u>Coboconk, Ontario</u>		GEOLOGIST <u>PW</u>	
CLIENT <u>Ministry of the Environment</u>		ELEVATION <u>276.94 masl</u>	

DEPTH (m)	STRATIGRAPHY	STRATIGRAPHIC DESCRIPTION	MONITOR DETAILS & NUMBER	SAMPLE						Penetration Resistance N VALUE (Blows/0.3m)	Water Content (%) w _c <input type="checkbox"/>		
				INTERVAL	NO.	TYPE	N VALUE	%RECOVERY	%WATER	%RQD			
											10	20	30
0.3		<u>SANDY SILT TOPSOIL</u>											
1		<u>LIMESTONE</u> (Gull River Formation) Grey, fractured with shaley partings and mud seams, fine to medium grained, laminated, fossiliferous			1	NQ		95		0			
					2	NQ		90		0			
2					3	NQ		80		47			
3					4	NQ		100		48			
4													
5					5	NQ		100		71			
6					6	NQ		100		74			
7													
8					7	NQ		100		80			
9.1													
9		NQ Corehole terminated at 9.1 m in fractured limestone.											

P-Piezometer S-Standpipe G-Gas Monitor

 Gartner Lee Limited

BOREHOLE LOG	PROJECT NO. <u>88-237</u>	BOREHOLE NO. <u>4</u>
PROJECT NAME <u>Coboconk Waste Disposal Site</u>		DATE <u>19 August 1988</u>
<u>Coboconk, Ontario</u>		GEOLOGIST <u>PW</u>
CLIENT <u>Ministry of the Environment</u>		ELEVATION <u>280.30 masl</u>

DEPTH (m)	STRATIGRAPHY	STRATIGRAPHIC DESCRIPTION	MONITOR DETAILS & NUMBER	SAMPLE						Penetration Resistance N VALUE (Blows/0.3m)	Water Content (%) w _c <input type="checkbox"/>
				NO.	TYPE	N VALUE	%RECOVERY	%WATER	%RQD		
0.2		<u>ORGANIC/SANDY TOPSOIL</u>									
1		<u>FILL</u> Tan-Brown to Brown, sand, gravel, silt, glass, rubble, garbage									
2											
3											
3.5				1	SS	60					> <input type="checkbox"/>
4		<u>LIMESTONE</u> (Gull River Formation) Grey, fractured with shaley partings and vuggy sections, fine to medium grained, laminated, fossiliferous		2	NQ	90			54		
5				3	NQ	100			56		
6											
7				4	NQ	100			67		
8											
9				5	NQ	100			74		
9.1		NQ Corehole terminated at 9.1 m in fractured limestone.									

P-Piezometer S-Standpipe G-Gas Monitor

TABLE 1: HAND AUGER HOLES
Coboconk Waste Disposal Site (88-237)

AH-1

0 - 0.15m Dark brown, clayey silt till with organic
 matter
 Gas reading = 0

AH-2

0 - 0.25m Brown, silty sand fill (roots, refuse -
 glass)
0.25 - 0.41m Brown, sandy silt/silty sand fill (refuse -
 glass, brick)
 Gas reading = 0

AH-3

0 - 0.15m Brown, silty sand fill
0.15 - 0.25m Brown, sandy silt fill (refuse - glass)
 Gas reading = 0

AH-4

0 - 0.25m Silty sand fill (refuse - burnt garbage and
 glass)
0.25 - 0.30m Tan-brown, fine to medium sand
 Gas reading = 0

AH-5

0 - 0.30m Brown, silty sand (refuse - glass)
 Gas reading = 0

AH-6

0 - 0.15m Black, organic, sandy topsoil
 Gas reading = 0

PROJECT NO: 88-237

MONITOR DETAILS SUMMARY

BOREHOLE		MONITOR					SCREENED INTERVAL		FILTER PACK		SEAL		BACKFILL	
NO.	DIAMETER (mm)	NO.	TYPE	DIAMETER (mm)	STICK-UP (m)	ELEVATION (t.o.p.m.)	(m)	(m)	(m)	(m)	(m)	(m)	(m)	(m)
1	76	I	PVC	51	0.32	281.114	9.8	- 8.3	9.8	- 8.0	8.0	- 7.4	7.4	- 0
1	76	II	PVC	51	0.04	280.916	6.1	- 3.1	6.1	- 3.0	3.0	- 2.4	2.4	- 0
2	76	I	PVC	51	0.22	277.194	9.0	- 7.5	9.0	- 7.0	7.0	- 6.4	6.4	- 0
2	76	II	PVC	51	0.08	277.087	4.6	- 1.6	4.6	- 1.0	1.0	- 0.4	0.4	- 0
3	76	I	PVC	51	0.37	277.305	8.7	- 7.2	8.7	- 7.0	7.0	- 6.4	6.4	- 0
3	76	II	PVC	51	0.31	277.315	4.3	- 1.3	4.3	- 1.0	1.0	- 0.4	0.4	- 0
4	76	I	PVC	51	0.09	280.388	8.8	- 5.8	8.8	- 5.5	5.5	- 4.9	4.9	- 0

NOTE: t.o.p.m. - TOP OF PIPE IN METRES


PROJECT NO: 88-237 COBOCONK LANDFILL

WATER LEVEL DATA

B.H. GROUND NO. ELEV.	MONITOR			18-AUG-88		19-AUG-88		23-AUG-88		24-AUG-88		25-AUG-88		11-NOV-88	
	NO.	TOP OF MONITOR ELEV.	TYPE	DEPTH BELOW T.O.P. (m)	ELEV. (m)	DEPTH BELOW T.O.P. (m)	ELEV. (m)	DEPTH BELOW T.O.P. (m)	ELEV. (m)	DEPTH BELOW T.O.P. (m)	ELEV. (m)	DEPTH BELOW T.O.P. (m)	ELEV. (m)	DEPTH BELOW T.O.P. (m)	ELEV. (m)
1 280.79	I	281.11	P	2.41	278.70	2.46	278.65	2.65	278.46	2.75	278.36	2.57	278.54	1.74	279.37
1 280.87	II	280.92	S	1.99	278.93	2.15	278.77	2.33	278.59	2.31	278.61	2.22	278.70	1.43	279.49
2 276.98	I	277.19	P	-	-	3.86	273.33	-	-	5.10	272.09	5.12	272.07	0.29	276.90
2 277.00	II	277.09	S	4.14	272.95	4.09	273.00	4.20	272.89	4.24	272.85	4.24	272.85	0.13	276.96
3 276.94	I	277.31	P	-	-	-	-	5.68	271.63	6.21	271.10	6.28	271.03	0.78	276.53
3 277.01	II	277.32	S	-	-	3.48	273.84	-	-	DRY	-	DRY	-	0.71	276.61
4 280.30	I	280.39	P	-	-	-	-	6.49	273.90	6.97	273.42	6.96	273.43	3.34	277.05


NOTE: S - STANDPIPE
P - PIEZOMETER
T.O.P. - TOP OF PIPE

SLUG TEST ANALYSIS - HVORSLEV'S METHOD




PROJECT NAME: COBOCONK PROJECT NUMBER: 88-237

SLUG TEST ANALYSIS - HVORSLEV'S METHOD




PROJECT NAME: COBOCONK PROJECT NUMBER: 88-237

SLUG TEST ANALYSIS - HVORSLEV'S METHOD




PROJECT NAME: COBOCONK LANDFILL SITE PROJECT NUMBER: 87-237

SLUG TEST ANALYSIS - HVORSLEV'S METHOD




PROJECT NAME: COBOCONK PROJECT NUMBER: 88237

SLUG TEST ANALYSIS - HVORSLEV'S METHOD




PROJECT NAME: COBOCONK PROJECT NUMBER: 88-237

SLUG TEST ANALYSIS - HVORSLEV'S METHOD



PROJECT NAME: COBOCONK LANDFILL SITE PROJECT NUMBER: 88237

SLUG TEST ANALYSIS - HVORSLEV'S METHOD



PROJECT NAME: COBOCONK PROJECT NUMBER: 88-237

APPENDIX IV

- **ROUTINE WATER CHEMISTRY ANALYSIS - AUGUST
SAMPLES**
- **ROUTINE WATER CHEMISTRY ANALYSES - NOVEMBER
SAMPLES**
- **VOLATILE ORGANIC ANALYSES OF LEACHATE
(MONITOR 4-I)**
- **HEAVY METAL ANALYSES OF LEACHATE
(MONITOR 4-I)**



MANN TESTING LABORATORIES LTD.

5550 MCADAM ROAD, MISSISSAUGA, ONTARIO L4Z 1P1

PHONE: 890-2555 • TELEX: 06-960496 • FAX: (416) 890-0370

CUSTOMER: Gartner Lee Limited
140 Renfrew Drive
Markham, Ontario
L3R 6B3

RECEIVED
OCT 18 1988
GARTNER LEE

REPORT #: 882315

CUSTOMER REF.# 88-237

ATTN: Mr. Rob Dickin

DATE SUBMITTED: Aug. 25, 1988

----- CERTIFICATE OF ANALYSIS -----

Sample Description: WATER

Preparation: Samples were prepared as recommended in APHA Standard methods for the examination of water and wastewater, 16th Edition, 1985 or MOE Handbook of analytical methods for environmental samples, 1983.

Note: Additional information is available on request.


Methodology:

Metals - flame, atomic absorption, Inductivity coupled Plasma Atomic Emission.

Conventionals - potentiometric, spectrophotometric and other wet chemical techniques.

Chemical Results: See Tables 1 and 2.

DATE: Oct. 6/88


CERTIFIED BY:
Jim Forrester,
Manager, Inorganic Dept.

REPORT TO: GARTNER LEE LIMITED
 PROJECT #:88-237
 LAB.#:882315
 TABLE #1A

RCap CHEMICAL PARAMETERS	METHOD DETECTION LIMIT	#H1		#H2	
		Water Soluble	'Total' Metals	Water Soluble	'Total' Metals
Sodium	0.5 mg/L	120		7.3	
Potassium	0.1 mg/L	5.0		1.9	
Calcium	0.005 mg/L	138		88	
Magnesium	0.001 mg/L	24		11	
Hardness (as CaCO ₃)	0.05 mg/L	443		265	
Alkalinity (as CaCO ₃)	1.0 mg/L	210		240	
Sulphate	1.0 mg/L	400		33	
Chloride	1.0 mg/L	54		8	
Silica	0.5 mg/L	10		6.1	
o-Phosphate (as P)	0.01 mg/L	<0.01		<0.01	
Nitrate + Nitrite (as N)	0.05 mg/L	<0.05		0.13	
Ammonia (as N)	0.05 mg/L	0.35		<0.05	
Iron	0.02 mg/L	0.23	0.31	0.02	0.05
Manganese	0.01 mg/L	0.04	0.05	<0.01	0.01
Copper	0.01 mg/L	<0.01	<0.01	0.11	0.11
Zinc	0.01 mg/L	0.27	0.30	0.01	0.01
Colour (true)	0.5 T.C.U.	6		6	
Turbidity	0.1 N.T.U.	2.5		0.6	
Conductivity (25°C)	0.1 umho/cm	1480		593	
pH	0.01	7.6		7.5	
Total Organic Carbon	0.5 mg/L	1.7		2.6	
Cation Sum	0.01 meq/L	14.27		5.68	
Anion Sum	0.01 meq/L	14.05		5.72	
Ion Ratio	0.01	1.02		0.99	
% Difference	0.1 %	0.8		0.4	
TDS (ion sum, calc)	0.1 mg/L	877		300	
Conductivity (calc, 25°C)	0.1 umho/cm	1632		568	
Saturation pH (4°C)	0.01	7.34		7.43	
Langelier Index (4°C)	0.01	0.26		0.07	
Bicarbonate(as CaCO ₃)	1.0 mg/L	209		239	
Carbonate(as CaCO ₃)	1.0 mg/L	0.8		0.7	

NOTE: ALL RESULTS BASED ON SAMPLE CENTRIFUGED AT 2000 RPM FOR 30 MINUTES
 EXCEPT pH, TURBIDITY, CONDUCTIVITY AND 'TOTAL METALS' (IRON, MANGANESE,
 COPPER AND ZINC)

ALL RESULTS BASED ON UNPRESERVED SAMPLE AS SUBMITTED EXCEPT FOR
 IRON, MANGANESE, COPPER AND ZINC (NITRIC ACID TO pH <2).

REPORT TO: GARTNER LEE LIMITED
 PROJECT #:88-237
 LAB. #:882315
 TABLE #1B

RCap CHEMICAL PARAMETERS	METHOD DETECTION LIMIT	#H3	#H4		
		Water Soluble	'Total' Metals	Water Soluble	'Total' Metals
Sodium	0.5 mg/L	84		58	
Potassium	0.1 mg/L	3.4		1.9	
Calcium	0.005 mg/L	129		134	
Magnesium	0.001 mg/L	13		8.3	
Hardness (as CaCO ₃)	0.05 mg/L	376		369	
Alkalinity (as CaCO ₃)	1.0 mg/L	280		230	
Sulphate	1.0 mg/L	49		140	
Chloride	1.0 mg/L	140		95	
Silica	0.5 mg/L	7.1		5.2	
o-Phosphate (as P)	0.01 mg/L	0.01		<0.01	
Nitrate + Nitrite (as N)	0.05 mg/L	2.9		2.2	
Ammonia (as N)	0.05 mg/L	<0.05		<0.05	
Iron	0.02 mg/L	0.08	0.19	0.01	0.03
Manganese	0.01 mg/L	0.15	0.16	0.02	0.01
Copper	0.01 mg/L	0.01	0.01	0.88	0.91
Zinc	0.01 mg/L	1.1	1.1	0.41	0.40
Colour (true)	0.5 T.C.U.	<3		6	
Turbidity	0.1 N.T.U.	1.1		0.5	
Conductivity (25°C)	0.1 umho/cm	1240		1128	
pH	0.01	7.4		7.5	
Total Organic Carbon	0.5 mg/L	3.9		2.8	
Cation Sum	0.01 meq/L	11.27		9.96	
Anion Sum	0.01 meq/L	10.77		10.35	
Ion Ratio	0.01	1.05		0.96	
% Difference	0.1 %	2.3		1.9	
TDS (ion sum, calc)	0.1 mg/L	606		590	
Conductivity (calc, 25°C)	0.1 umho/cm	1205		1138	
Saturation pH (4°C)	0.01	7.23		7.29	
Langelier Index (4°C)	0.01	0.17		0.21	
Bicarbonate(as CaCO ₃)	1.0 mg/L	279		229	
Carbonate(as CaCO ₃)	1.0 mg/L	0.7		0.7	

NOTE: ALL RESULTS BASED ON SAMPLE CENTRIFUGED AT 2000 RPM FOR 30 MINUTES
 EXCEPT pH, TURBIDITY, CONDUCTIVITY AND 'TOTAL METALS' (IRON, MANGANESE,
 COPPER AND ZINC)

ALL RESULTS BASED ON UNPRESERVED SAMPLE AS SUBMITTED EXCEPT FOR
 IRON, MANGANESE, COPPER AND ZINC (NITRIC ACID TO pH <2).

REPORT TO: GARTNER LEE LIMITED
 PROJECT #:88-237
 LAB.#:882315
 TABLE #1C

RCap CHEMICAL PARAMETERS	METHOD DETECTION LIMIT	#H5		#H6	
		Water Soluble	'Total' Metals	Water Soluble	'Total' Metals
Sodium	0.5 mg/L	14		170	
Potassium	0.1 mg/L	4.1		3.7	
Calcium	0.005 mg/L	94		200	
Magnesium	0.001 mg/L	20		9.8	
Hardness (as CaCO ₃)	0.05 mg/L	317		540	
Alkalinity (as CaCO ₃)	1.0 mg/L	250		350	
Sulphate	1.0 mg/L	67		35	
Chloride	1.0 mg/L	22		360	
Silica	0.5 mg/L	7.9		6.2	
o-Phosphate (as P)	0.01 mg/L	<0.01		0.04	
Nitrate + Nitrite (as N)	0.05 mg/L	0.17		0.69	
Ammonia (as N)	0.05 mg/L	0.19		0.93	
Iron	0.02 mg/L	0.10	0.36	0.09	0.64
Manganese	0.01 mg/L	0.04	0.05	0.35	0.46
Copper	0.01 mg/L	0.28	0.29	0.15	0.17
Zinc	0.01 mg/L	1.1	1.10	0.03	0.03
Colour (true)	0.5 T.C.U.	11		12	
Turbidity	0.1 N.T.U.	4.4		3.1	
Conductivity (25°C)	0.1 umho/cm	760		1960	
pH	0.01	7.5		7.2	
Total Organic Carbon	0.5 mg/L	4.1		4.5	
Cation Sum	0.01 meq/L	7.09		18.37	
Anion Sum	0.01 meq/L	7.03		17.92	
Ion Ratio	0.01	1.01		1.03	
% Difference	0.1 %	0.4		1.2	
TDS (ion sum, calc)	0.1 mg/L	380		999	
Conductivity (calc, 25°C)	0.1 umho/cm	729		2064	
Saturation pH (4°C)	0.01	7.39		6.97	
Langelier Index (4°C)	0.01	0.11		0.23	
Bicarbonate(as CaCO ₃)	1.0 mg/L	249		350	
Carbonate(as CaCO ₃)	1.0 mg/L	0.7		0.5	

NOTE: ALL RESULTS BASED ON SAMPLE CENTRIFUGED AT 2000 RPM FOR 30 MINUTES
 EXCEPT pH, TURBIDITY, CONDUCTIVITY AND 'TOTAL METALS' (IRON, MANGANESE,
 COPPER AND ZINC)

ALL RESULTS BASED ON UNPRESERVED SAMPLE AS SUBMITTED EXCEPT FOR
 IRON, MANGANESE, COPPER AND ZINC (NITRIC ACID TO pH <2).

REPORT TO: GARTNER LEE LIMITED
 PROJECT #:88-237
 LAB. #:882315
 TABLE #1D

RCap CHEMICAL PARAMETERS	METHOD DETECTION LIMIT	#H7		#H8	
		Water Soluble	'Total' Metals	Water Soluble	'Total' Metals
Sodium	0.5 mg/L	22		16	
Potassium	0.1 mg/L	3.0		2.4	
Calcium	0.005 mg/L	112		111	
Magnesium	0.001 mg/L	13		6.6	
Hardness (as CaCO ₃)	0.05 mg/L	333		304	
Alkalinity (as CaCO ₃)	1.0 mg/L	250		230	
Sulphate	1.0 mg/L	75		65	
Chloride	1.0 mg/L	41		20	
Silica	0.5 mg/L	5.6		5.0	
o-Phosphate (as P)	0.01 mg/L	<0.01		0.02	
Nitrate + Nitrite (as N)	0.05 mg/L	<0.05		5.2	
Ammonia (as N)	0.05 mg/L	0.14		<0.05	
Iron	0.02 mg/L	0.40	1.0	0.02	0.03
Manganese	0.01 mg/L	0.06	0.11	0.02	0.01
Copper	0.01 mg/L	0.01	0.02	0.01	0.01
Zinc	0.01 mg/L	0.60	0.74	0.06	0.06
Colour (true)	0.5 T.C.U.	22		10	
Turbidity	0.1 N.T.U.	3.2		0.6	
Conductivity (25°C)	0.1 umho/cm	770		760	
pH	0.01	7.4		7.6	
Total Organic Carbon	0.5 mg/L	5.9		3.3	
Cation Sum	0.01 meq/L	7.73		6.86	
Anion Sum	0.01 meq/L	7.72		6.89	
Ion Ratio	0.01	1.00		1.00	
% Difference	0.1 %	0.1		0.2	
TDS (ion sum, calc)	0.1 mg/L	422		387	
Conductivity (calc, 25°C)	0.1 umho/cm	816		723	
Saturation pH (4°C)	0.01	7.32		7.36	
Langelier Index (4°C)	0.01	0.08		0.24	
Bicarbonate(as CaCO ₃)	1.0 mg/L	249		229	
Carbonate(as CaCO ₃)	1.0 mg/L	0.6		0.9	

NOTE: ALL RESULTS BASED ON SAMPLE CENTRIFUGED AT 2000 RPM FOR 30 MINUTES
 EXCEPT pH, TURBIDITY, CONDUCTIVITY AND 'TOTAL METALS' (IRON, MANGANESE,
 COPPER AND ZINC)

ALL RESULTS BASED ON UNPRESERVED SAMPLE AS SUBMITTED EXCEPT FOR
 IRON, MANGANESE, COPPER AND ZINC (NITRIC ACID TO pH <2).

REPORT TO: GARTNER LEE LIMITED
 PROJECT #:88-237
 LAB.#:882315
 TABLE #1E

RCap CHEMICAL PARAMETERS	METHOD DETECTION LIMIT	#H9	1-I #BH 1-D		
		Water Soluble	'Total' Metals	Water Soluble	'Total' Metals
Sodium	0.5 mg/L	160		0.9	
Potassium	0.1 mg/L	3.7		0.6	
Calcium	0.005 mg/L	197		113	
Magnesium	0.001 mg/L	9.7		3.8	
Hardness (as CaCO ₃)	0.05 mg/L	532		298	
Alkalinity (as CaCO ₃)	1.0 mg/L	350		290	
Sulphate	1.0 mg/L	34		15	
Chloride	1.0 mg/L	360		2	
Silica	0.5 mg/L	6.2		4.8	
o-Phosphate (as P)	0.01 mg/L	0.04		<0.01	
Nitrate + Nitrite (as N)	0.05 mg/L	0.73		<0.05	
Ammonia (as N)	0.05 mg/L	0.95		<0.05	
Iron	0.02 mg/L	0.07	0.64	0.07	0.95
Manganese	0.01 mg/L	0.34	0.45	0.06	0.15
Copper	0.01 mg/L	0.16	0.19	<0.01	<0.01
Zinc	0.01 mg/L	0.03	0.03	0.01	0.01
Colour (true)	0.5 T.C.U.	12		10	
Turbidity	0.1 N.T.U.	2.8		180	
Conductivity (25°C)	0.1 umho/cm	1990		625	
pH	0.01	7.3		7.5	
Total Organic Carbon	0.5 mg/L	4.5		4.1	
Cation Sum	0.01 meq/L	17.78		6.02	
Anion Sum	0.01 meq/L	17.90		6.17	
Ion Ratio	0.01	0.99		0.98	
% Difference	0.1 %	0.3		1.2	
TDS (ion sum, calc)	0.1 mg/L	985		314	
Conductivity (calc, 25°C)	0.1 umho/cm	2034		592	
Saturation pH (4°C)	0.01	6.97		7.24	
Langelier Index (4°C)	0.01	0.33		0.26	
Bicarbonate(as CaCO ₃)	1.0 mg/L	349		289	
Carbonate(as CaCO ₃)	1.0 mg/L	0.7		0.9	

NOTE: ALL RESULTS BASED ON SAMPLE CENTRIFUGED AT 2000 RPM FOR 30 MINUTES
 EXCEPT pH, TURBIDITY, CONDUCTIVITY AND 'TOTAL METALS' (IRON, MANGANESE,
 COPPER AND ZINC)

ALL RESULTS BASED ON UNPRESERVED SAMPLE AS SUBMITTED EXCEPT FOR
 IRON, MANGANESE, COPPER AND ZINC (NITRIC ACID TO pH <2).

REPORT TO: GARTNER LEE LIMITED
 PROJECT #:88-237
 LAB.#:882315
 TABLE #1F

RCap CHEMICAL PARAMETERS	METHOD DETECTION LIMIT	1-II		2-I	
		#BH 1-S	'Total' Metals	#BH 2-D	'Total' Metals
		Water Soluble		Water Soluble	
Sodium	0.5 mg/L	0.9		20	
Potassium	0.1 mg/L	3.5		3.7	
Calcium	0.005 mg/L	99		64	
Magnesium	0.001 mg/L	7.8		14	
Hardness (as CaCO ₃)	0.05 mg/L	279		218	
Alkalinity (as CaCO ₃)	1.0 mg/L	250		175	
Sulphate	1.0 mg/L	21		70	
Chloride	1.0 mg/L	3		11	
Silica	0.5 mg/L	5.3		4.7	
o-Phosphate (as P)	0.01 mg/L	<0.01		<0.01	
Nitrate + Nitrite (as N)	0.05 mg/L	<0.05		0.86	
Ammonia (as N)	0.05 mg/L	<0.05		0.4	
Iron	0.02 mg/L	0.02	0.23	0.03	0.61
Manganese	0.01 mg/L	0.04	0.05	0.04	0.11
Copper	0.01 mg/L	0.01	0.01	0.01	0.02
Zinc	0.01 mg/L	0.02	0.02	0.01	0.03
Colour (true)	0.5 T.C.U.	11		4	
Turbidity	0.1 N.T.U.	52		100	
Conductivity (25°C)	0.1 umho/cm	575		560	
pH	0.01	7.6		7.7	
Total Organic Carbon	0.5 mg/L	2.9		4.1	
Cation Sum	0.01 meq/L	5.73		5.36	
Anion Sum	0.01 meq/L	5.51		5.33	
Ion Ratio	0.01	1.04		1.01	
% Difference	0.1 %	2.0		0.3	
TDS (ion sum, calc)	0.1 mg/L	290		297	
Conductivity (calc, 25°C)	0.1 umho/cm	552		558	
Saturation pH (4°C)	0.01	7.36		7.70	
Langelier Index (4°C)	0.01	0.24		0.00	
Bicarbonate(as CaCO ₃)	1.0 mg/L	249		174	
Carbonate(as CaCO ₃)	1.0 mg/L	0.9		0.8	

NOTE: ALL RESULTS BASED ON SAMPLE CENTRIFUGED AT 2000 RPM FOR 30 MINUTES
 EXCEPT pH, TURBIDITY, CONDUCTIVITY AND 'TOTAL METALS' (IRON, MANGANESE,
 COPPER AND ZINC)

ALL RESULTS BASED ON UNPRESERVED SAMPLE AS SUBMITTED EXCEPT FOR
 IRON, MANGANESE, COPPER AND ZINC (NITRIC ACID TO pH <2).

REPORT TO: GARTNER LEE LIMITED
 PROJECT #:88-237
 LAB.#:882315
 TABLE #1G

3-I

RCap CHEMICAL PARAMETERS	METHOD DETECTION LIMIT	#BH 3-D	#BH 4		
		Water Soluble	'Total' Metals	Water Soluble	'Total' Metals
Sodium	0.5 mg/L	7.6		4	
Potassium	0.1 mg/L	6.3		3.4	
Calcium	0.005 mg/L	86		88	
Magnesium	0.001 mg/L	12		21	
Hardness (as CaCO ₃)	0.05 mg/L	264		306	
Alkalinity (as CaCO ₃)	1.0 mg/L	190		280	
Sulphate	1.0 mg/L	70		26	
Chloride	1.0 mg/L	11		4	
Silica	0.5 mg/L	5.0		8.3	
o-Phosphate (as P)	0.01 mg/L	<0.01		<0.01	
Nitrate + Nitrite (as N)	0.05 mg/L	0.56		0.11	
Ammonia (as N)	0.05 mg/L	0.25		0.23	
Iron	0.02 mg/L	0.06	2.0	0.05	1.6
Manganese	0.01 mg/L	0.03	0.50	0.04	0.14
Copper	0.01 mg/L	<0.01	0.02	<0.01	0.01
Zinc	0.01 mg/L	0.01	0.04	0.01	0.04
Colour (true)	0.5 T.C.U.	4		5	
Turbidity	0.1 N.T.U.	>1000		99	
Conductivity (25°C)	0.1 umho/cm	660		640	
pH	0.01	7.5		7.5	
Total Organic Carbon	0.5 mg/L	5.4		2.6	
Cation Sum	0.01 meq/L	5.81		6.43	
Anion Sum	0.01 meq/L	5.61		6.25	
Ion Ratio	0.01	1.04		1.03	
% Difference	0.1 %	1.8		1.4	
TDS (ion sum, calc)	0.1 mg/L	315		323	
Conductivity (calc, 25°C)	0.1 umho/cm	598		618	
Saturation pH (4°C)	0.01	7.54		7.36	
Langelier Index (4°C)	0.01	-0.04		0.14	
Bicarbonate(as CaCO ₃)	1.0 mg/L	189		279	
Carbonate(as CaCO ₃)	1.0 mg/L	0.6		0.8	

NOTE: ALL RESULTS BASED ON SAMPLE CENTRIFUGED AT 2000 RPM FOR 30 MINUTES
 EXCEPT pH, TURBIDITY, CONDUCTIVITY AND 'TOTAL METALS' (IRON, MANGANESE,
 COPPER AND ZINC)

ALL RESULTS BASED ON UNPRESERVED SAMPLE AS SUBMITTED EXCEPT FOR
 IRON, MANGANESE, COPPER AND ZINC (NITRIC ACID TO pH <2).

REPORT TO: GARTNER LEE LIMITED
 PROJECT #:88-237
 LAB.#:882315
 TABLE #1H

RCap CHEMICAL PARAMETERS	METHOD DETECTION LIMIT	#BH 5		#BH 6	
		Water Soluble	'Total' Metals	Water Soluble	'Total' Metals
Sodium	0.5 mg/L	8.8		0.6	
Potassium	0.1 mg/L	1.2		0.4	
Calcium	0.005 mg/L	36		75	
Magnesium	0.001 mg/L	8.3		3.6	
Hardness (as CaCO ₃)	0.05 mg/L	124		202	
Alkalinity (as CaCO ₃)	1.0 mg/L	85		195	
Sulphate	1.0 mg/L	26		11	
Chloride	1.0 mg/L	25		2	
Silica	0.5 mg/L	0.8		4.8	
o-Phosphate (as P)	0.01 mg/L	<0.01		<0.01	
Nitrate + Nitrite (as N)	0.05 mg/L	0.24		<0.05	
Ammonia (as N)	0.05 mg/L	0.19		<0.05	
Iron	0.02 mg/L	0.02	0.03	0.04	1.7
Manganese	0.01 mg/L	0.01	<0.01	0.06	0.25
Copper	0.01 mg/L	0.01	0.01	<0.01	<0.01
Zinc	0.01 mg/L	0.01	<0.01	<0.01	0.01
Colour (true)	0.5 T.C.U.	<3		18	
Turbidity	0.1 N.T.U.	15		290	
Conductivity (25°C)	0.1 umho/cm	300		430	
pH	0.01	7.6		7.3	
Total Organic Carbon	0.5 mg/L	2.6		3.5	
Cation Sum	0.01 meq/L	2.92		4.09	
Anion Sum	0.01 meq/L	2.96		4.19	
Ion Ratio	0.01	0.99		0.98	
% Difference	0.1 %	0.7		1.2	
TDS (ion sum, calc)	0.1 mg/L	158		215	
Conductivity (calc, 25°C)	0.1 umho/cm	316		402	
Saturation pH (4°C)	0.01	8.25		7.58	
Langelier Index (4°C)	0.01	-0.65		-0.28	
Bicarbonate(as CaCO ₃)	1.0 mg/L	85		195	
Carbonate(as CaCO ₃)	1.0 mg/L	0.3		0.4	

NOTE: ALL RESULTS BASED ON SAMPLE CENTRIFUGED AT 2000 RPM FOR 30 MINUTES
 EXCEPT pH, TURBIDITY, CONDUCTIVITY AND 'TOTAL METALS' (IRON, MANGANESE,
 COPPER AND ZINC)

ALL RESULTS BASED ON UNPRESERVED SAMPLE AS SUBMITTED EXCEPT FOR
 IRON, MANGANESE, COPPER AND ZINC (NITRIC ACID TO pH <2) .

REPORT TO: GARTNER LEE LIMITED
 PROJECT #:88-237
 LAB.#:882315
 TABLE #1I

RCap CHEMICAL PARAMETERS	METHOD DETECTION LIMIT	#Q 1		#R 2	
		Water Soluble	'Total' Metals	Water Soluble	'Total' Metals
Sodium	0.5 mg/L	15		1.5	
Potassium	0.1 mg/L	3.7		0.7	
Calcium	0.005 mg/L	82		9	
Magnesium	0.001 mg/L	18		1.8	
Hardness (as CaCO ₃)	0.05 mg/L	279		29	
Alkalinity (as CaCO ₃)	1.0 mg/L	140		19	
Sulphate	1.0 mg/L	150		11	
Chloride	1.0 mg/L	19		3	
Silica	0.5 mg/L	1.5		1.4	
o-Phosphate (as P)	0.01 mg/L	0.07		<0.01	
Nitrate + Nitrite (as N)	0.05 mg/L	2.5		<0.05	
Ammonia (as N)	0.05 mg/L	0.10		0.05	
Iron	0.02 mg/L	0.05	0.07	0.04	0.07
Manganese	0.01 mg/L	0.02	0.01	0.01	0.02
Copper	0.01 mg/L	<0.01	<0.01	0.01	0.01
Zinc	0.01 mg/L	0.01	0.01	0.01	0.01
Colour (true)	0.5 T.C.U.	<3		11	
Turbidity	0.1 N.T.U.	2.4		1.1	
Conductivity (25°C)	0.1 umho/cm	740		73	
pH	0.01	8.0		7.5	
Total Organic Carbon	0.5 mg/L	4.7		4.6	
Cation Sum	0.01 meq/L	6.35		0.67	
Anion Sum	0.01 meq/L	6.64		0.69	
Ion Ratio	0.01	0.96		0.97	
% Difference	0.1 %	2.2		1.5	
TDS (ion sum, calc)	0.1 mg/L	384		40	
Conductivity (calc, 25°C)	0.1 umho/cm	729		74	
Saturation pH (4°C)	0.01	7.70		9.49	
Langelier Index (4°C)	0.01	0.30		-1.99	
Bicarbonate(as CaCO ₃)	1.0 mg/L	139		19	
Carbonate(as CaCO ₃)	1.0 mg/L	1.3		0.1	

NOTE: ALL RESULTS BASED ON SAMPLE CENTRIFUGED AT 2000 RPM FOR 30 MINUTES
 EXCEPT pH, TURBIDITY, CONDUCTIVITY AND 'TOTAL METALS' (IRON, MANGANESE,
 COPPER AND ZINC)

ALL RESULTS BASED ON UNPRESERVED SAMPLE AS SUBMITTED EXCEPT FOR
 IRON, MANGANESE, COPPER AND ZINC (NITRIC ACID TO pH <2).

REPORT TO: GARTNER LEE LIMITED
 PROJECT #:88-237
 LAB.#:882315
 TABLE #1J

RCap CHEMICAL PARAMETERS	METHOD DETECTION LIMIT	#R 3		#R 4	
		Water Soluble	'Total' Metals	Water Soluble	'Total' Metals
Sodium	0.5 mg/L	1.8		1.3	
Potassium	0.1 mg/L	0.6		0.5	
Calcium	0.005 mg/L	9		8	
Magnesium	0.001 mg/L	1.7		1.7	
Hardness (as CaCO ₃)	0.05 mg/L	30		26	
Alkalinity (as CaCO ₃)	1.0 mg/L	21		16	
Sulphate	1.0 mg/L	10		10	
Chloride	1.0 mg/L	3		3	
Silica	0.5 mg/L	1.4		1.4	
o-Phosphate (as P)	0.01 mg/L	<0.01		<0.01	
Nitrate + Nitrite (as N)	0.05 mg/L	<0.05		<0.05	
Ammonia (as N)	0.05 mg/L	<0.05		<0.05	
Iron	0.02 mg/L	0.04	0.30	0.03	0.04
Manganese	0.01 mg/L	0.01	0.05	0.01	0.01
Copper	0.01 mg/L	<0.01	<0.01	<0.01	<0.01
Zinc	0.01 mg/L	<0.01	<0.01	<0.01	<0.01
Colour (true)	0.5 T.C.U.	12		11	
Turbidity	0.1 N.T.U.	4		0.6	
Conductivity (25°C)	0.1 umho/cm	76		65	
pH	0.01	7.9		7.4	
Total Organic Carbon	0.5 mg/L	4.2		4.1	
Cation Sum	0.01 meq/L	0.70		0.59	
Anion Sum	0.01 meq/L	0.71		0.60	
Ion Ratio	0.01	0.99		0.98	
% Difference	0.1 %	0.7		0.8	
TDS (ion sum, calc)	0.1 mg/L	40		35	
Conductivity (calc, 25°C)	0.1 umho/cm	75		65	
Saturation pH (4°C)	0.01	9.42		9.62	
Langelier Index (4°C)	0.01	-1.52		-2.22	
Bicarbonate(as CaCO ₃)	1.0 mg/L	21		16	
Carbonate(as CaCO ₃)	1.0 mg/L	0.2		0.0	

NOTE: ALL RESULTS BASED ON SAMPLE CENTRIFUGED AT 2000 RPM FOR 30 MINUTES
 EXCEPT pH, TURBIDITY, CONDUCTIVITY AND 'TOTAL METALS' (IRON, MANGANESE,
 COPPER AND ZINC)

ALL RESULTS BASED ON UNPRESERVED SAMPLE AS SUBMITTED EXCEPT FOR
 IRON, MANGANESE, COPPER AND ZINC (NITRIC ACID TO pH <2).

GEN-V

CLIENT: GARTNER & LEE ASSOCIATES

REF. NO.: 882315

TABLE: 2

CHEMICAL PARAMETERS - GENERAL

SAMPLE IDENTIFICATION	PHENOLS mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
H1	<0.002							
H2	<0.002							
H3	0.006							
H4	<0.002							
H5	0.003							
H6	0.003							
H7	0.003							
H8	<0.002							
H9	<0.002							
BH1-D 1-I	<0.002							
BH1-S 1-II	<0.002							
BH2-D 2-I	0.006							
BH3-D 3-I	0.003							
BH4	0.003							
BH5	0.003							
BH6	<0.002							
Q1	<0.002							
R2	<0.002							
R3	<0.002							
R4	<0.002							

QA/QC PROTOCOL

0.0288	0.0275							
TRUE VALUE								
TRUE VALUE								
TRUE VALUE								

MDL

MDL = INSTRUMENT/METHOD DETECTION LIMIT

NS = NON SUFFICIENT SAMPLE

-- = NO ANALYSIS REQUIRED



MANN AQUA LABORATORIES LTD.
5550 McADAM ROAD, MISSISSAUGA, ONTARIO L4Z 1P1
PHONE: (416) 890-2555 · TELEX: 06-960496 · FAX: (416) 890-0370

NEW ADDRESS:
UNIT #6
400 MATHESON BLVD. EAST
MISSISSAUGA, ONT. L4Z 1N8

CLIENT: Gartner Lee Limited
140 Renfrew Drive
Markham, Ontario
L3R 8B6

REPORT #: MA01902-1905

CUSTOMER REF.#88-237

ATTN: Mr. Rob Dickin

DATE SUBMITTED: Nov 15/88

-----CERTIFICATE OF ANALYSIS-----

Sample Description: WATER

Preparation: Samples were prepared as recommended in APHA Standard Methods for the Examination of Water and Wastewater, 16th Edition, 1985 unless otherwise noted.

Methodology: Rapid Chemical Analysis program (RCap)

Chemical Results: See Tables 1A and 1B

Note: If you require further information, please contact Nora Macnee at (416) 890-2555.

DATE: January 23, 1989

J. Dale

CERTIFIED BY:
Jim Dale, M.Sc.
Manager, RCap

REPORT TO: GARTNER LEE LIMITED
 PROJECT #:88-237
 LAB. #:MA01902-1903
 TABLE #1A

RCAP CHEMICAL PARAMETERS	METHOD DETECTION LIMIT	SAMPLE #BH 2-II		SAMPLE #BH 3-II	
		Water Soluble	'Total' Metals	Water Soluble	'Total' Metals
Sodium	0.5 mg/L	25		25	
Potassium	0.1 mg/L	2.1		23	
Calcium	0.005 mg/L	64		137	
Magnesium	0.001 mg/L	5.7		14	
Hardness (as CaCO ₃)	0.05 mg/L	185		404	
Alkalinity (as CaCO ₃)	1.0 mg/L	199		294	
Sulphate	1.0 mg/L	49		176	
Chloride	1.0 mg/L	3.0		10	
Silica	0.5 mg/L	4.2		5.6	
o-Phosphate (as P)	0.01 mg/L	<0.01		<0.01	
Nitrate + Nitrite (as N)	0.05 mg/L	0.22		4.6	
Ammonia (as N)	0.05 mg/L	<0.05		<0.05	
Iron	0.02 mg/L	0.03	0.09	0.03	0.97
Manganese	0.01 mg/L	0.03	0.03	0.04	0.13
Copper	0.01 mg/L	0.01	0.01	0.01	0.01
Zinc	0.01 mg/L	0.01	0.01	0.03	0.04
Colour (true)	0.5 T.C.U.	5		<3	
Turbidity	0.1 N.T.U.	13		17	
Conductivity (25°C)	0.1 umho/cm	522		1098	
pH	0.01	8.0		7.6	
Total Organic Carbon	0.5 mg/L	2.0		5.6	
Cation Sum	0.01 meq/L	4.86		9.76	
Anion Sum	0.01 meq/L	5.09		10.12	
Ion Ratio	0.01	0.95		0.97	
% Difference	0.1 %	2.4		1.8	
TDS (ion sum, calc)	0.1 mg/L	396		769	
Conductivity (calc, 25°C)	0.1 umho/cm	505		1080	
Saturation pH (4°C)	0.01	7.77		7.31	
Langelier Index (4°C)	0.01	0.23		0.29	
Bicarbonate(as CaCO ₃)	1.0 mg/L	197		292	
Carbonate(as CaCO ₃)	1.0 mg/L	1.9		1.1	

NOTE: ALL RESULTS BASED ON SAMPLE CENTRIFUGED AT 2000 RPM FOR 30 MINUTES
 EXCEPT pH, TURBIDITY, CONDUCTIVITY AND 'TOTAL METALS' (IRON, MANGANESE,
 COPPER AND ZINC)

ALL RESULTS BASED ON UNPRESERVED SAMPLE AS SUBMITTED EXCEPT FOR
 IRON, MANGANESE, COPPER AND ZINC (NITRIC ACID TO pH <2).

REPORT TO: GARTNER LEE LIMITED
 PROJECT #:88-237
 LAB.#:MA01904-1905
 TABLE #1B

RCap CHEMICAL PARAMETERS	METHOD DETECTION LIMIT	SAMPLE #BH 4		SAMPLE #SW A	
		Water Soluble	'Total' Metals	Water Soluble	'Total' Metals
Sodium	0.5 mg/L	3.3		10	
Potassium	0.1 mg/L	11		4.0	
Calcium	0.005 mg/L	117		104	
Magnesium	0.001 mg/L	10		3.0	
Hardness (as CaCO ₃)	0.05 mg/L	334		273	
Alkalinity (as CaCO ₃)	1.0 mg/L	321		294	
Sulphate	1.0 mg/L	33		18	
Chloride	1.0 mg/L	1.0		<1.0	
Silica	0.5 mg/L	6.5		4.0	
o-Phosphate (as P)	0.01 mg/L	<0.01		<0.01	
Nitrate + Nitrite (as N)	0.05 mg/L	0.74		<0.05	
Ammonia (as N)	0.05 mg/L	0.09		<0.05	
Iron	0.02 mg/L	0.02	3.20	0.02	0.03
Manganese	0.01 mg/L	0.06	0.28	0.04	0.04
Copper	0.01 mg/L	0.01	0.07	0.01	0.01
Zinc	0.01 mg/L	0.08	0.16	0.01	0.01
Colour (true)	0.5 T.C.U.	<3		5	
Turbidity	0.1 N.T.U.	72		0.6	
Conductivity (25°C)	0.1 umho/cm	766		570	
pH	0.01	7.6		7.7	
Total Organic Carbon	0.5 mg/L	2.0		3.7	
Cation Sum	0.01 meq/L	7.12		5.99	
Anion Sum	0.01 meq/L	7.19		6.24	
Ion Ratio	0.01	0.99		0.96	
% Difference	0.1 %	0.5		2.1	
TDS (ion sum, calc)	0.1 mg/L	576		500	
Conductivity (calc, 25°C)	0.1 umho/cm	708		595	
Saturation pH (4°C)	0.01	7.32		7.41	
Langelier Index (4°C)	0.01	0.28		0.29	
Bicarbonate(as CaCO ₃)	1.0 mg/L	320		292	
Carbonate(as CaCO ₃)	1.0 mg/L	1.2		1.4	


NOTE: ALL RESULTS BASED ON SAMPLE CENTRIFUGED AT 2000 RPM FOR 30 MINUTES
 EXCEPT pH, TURBIDITY, CONDUCTIVITY AND 'TOTAL METALS' (IRON, MANGANESE,
 COPPER AND ZINC)

ALL RESULTS BASED ON UNPRESERVED SAMPLE AS SUBMITTED EXCEPT FOR
 IRON, MANGANESE, COPPER AND ZINC (NITRIC ACID TO pH <2).



MANN TESTING LABORATORIES LTD.

5550 McADAM ROAD, MISSISSAUGA, ONTARIO L4G 1P1
PHONE: 890-2555 • TELEX: 06-960496 • FAX: (416) 890-0370



CUSTOMER: Gartner Lee Limited
140 Renfrew Drive
Suite 102
Markham, Ontario
L3R 8B6

REPORT #: 883893

CUSTOMER REF.# 88-237

ATTN: Mr. Rob Dickin

DATE SUBMITTED: Nov. 17, 1988

----- CERTIFICATE OF ANALYSIS -----

Sample Description: WATER

Preparation: Samples were prepared as recommended in APHA Standard methods for the examination of water and wastewater, 16th Edition, 1985 or MOE Handbook of analytical methods for environmental samples, 1983.

Note: Additional information is available on request.

Methodology:

Conventionals - wet chemical techniques.

Chemical Results: See Table 1.

DATE: Dec. 21, 1988



CERTIFIED BY:
Jim Forrester,
Manager, Inorganic Dept.

TABLE: 1

CHEMICAL ANALYSIS - GENERAL

CONC = mg/L UNLESS OTHERWISE NOTED

CHEMICAL PARAMETERS	MDL (mg/L)	QA/QC (mg/L)		BH2-II	BH3-II	BH4		
		EXP'T	TRUE					
Phenol	0.002	0.028	0.029(e)	<0.002	<0.002	<0.002		

MDL = INSTRUMENT/METHOD DETECTION LIMIT

NS = NON SUFFICIENT SAMPLE

-- = NO ANALYSIS REQUIRED

a= EPA WP 1083

b= EPA WP 386

c= NBS 1643b

d= EPA WP 1185+WS 378

e= OTHER

ICAP 19/7

TRACE METALS - I

TRACE ELEMENTS IN WATER

MINERALS +NO3/F-6




MANN TESTING LABORATORIES LTD.

5550 McADAM ROAD, MISSISSAUGA, ONTARIO L4Z 1P1

PHONE: 890-2555 • TELEX: 06-960496 • FAX: (416) 890-0370

CUSTOMER: Gartner Lee Limited
140 Renfrew Drive
Suite 102
Markham, Ontario
L3R 6B3

ENV-003



ATTN: Mr. Rob Dicken

REPORT #: 882319

CUSTOMER REF.#

DATE SUBMITTED: Aug. 25, 1988

DATE REPORTED: Sept. 28/88

----- **CERTIFICATE OF ANALYSIS** -----

Sample Description: WATER

Analysis Performed: VOLATILE ORGANIC ANALYSIS

Protocol based upon U.S. EPA Method #624.
Samples are fortified with isotopically labelled
internal standards and analyzed by purge and trap
gas chromatography/mass spectrometry (PT-GC/MS).

Note: Additional information is available on request.

Instrumentation:

- Envirochem 810 purge and trap concentrator.
- Finnigan 3200 GC/MS-DS.


Chemical Results: See Table V-1.

Nellie Sio

CERTIFIED BY:
Nellie Sio, B. Tech
Project Leader-Volatile Organics

Tim Munshaw

WITNESSED BY:
Tim Munshaw, M.Sc. C. Chem.
Manager, Environmental Dept.



* Refer inquiries to.

2319-V-1

VOLATILE ORGANICS

Conc. = (ppb)

GARTNER LEE LIMITED

W.O. #882319

VOLATILE COMPOUNDS	MDL	TRAVELLING			
	(ppb)	BLANK	BH-4		
DICHLORODIFLUOROMETHANE	2.0	--	--	--	--
CHLOROMETHANE	2.0	--	--	--	--
VINYL CHLORIDE	2.0	--	--	--	--
BROMOMETHANE	2.0	--	--	--	--
CHLOROETHANE	2.0	--	--	--	--
TRICHLOROFLUOROMETHANE	2.0	--	--	--	--
1,1-DICHLOROETHYLENE	1.0	--	--	--	--
DICHLOROMETHANE	1.0	4.24	--	--	--
T-1,2-DICHLOROETHYLENE	1.0	--	--	--	--
1,1-DICHLOROETHANE	1.0	--	--	--	--
CHLOROFORM	1.0	TR	--	--	--
1,2-DICHLOROETHANE	1.0	--	--	--	--
1,1,1-TRICHLOROETHANE	1.0	--	--	--	--
BENZENE	0.5	TR	TR	--	--
CARBON TETRACHLORIDE	1.0	--	--	--	--
1,2-DICHLOROPROPANE	1.0	--	--	--	--
BROMODICHLOROMETHANE	1.0	--	--	--	--
TRICHLOROETHYLENE	1.0	--	--	--	--
1,3-DICHLOROPROPENE(Z)	1.0	--	--	--	--
1,3-DICHLOROPROPENE(E)	1.0	--	--	--	--
1,1,2-TRICHLOROETHANE	1.0	--	--	--	--
TOLUENE	0.5	--	--	--	--
DIBROMOCHLOROMETHANE	1.0	--	--	--	--
TETRACHLOROETHYLENE	1.0	--	--	--	--
CHLOROBENZENE	0.5	--	--	--	--
ETHYL BENZENE	0.5	--	--	--	--
P & M XYLENE	0.5	--	--	--	--
BROMOFORM	1.0	--	--	--	--
O-XYLENE	0.5	--	--	--	--
1,1,2,2-TETRACHLOROETHANE	1.0	--	--	--	--
1,3-DICHLOROBENZENE	1.0	--	--	--	--
1,4-DICHLOROBENZENE	1.0	--	TR	--	--
1,2-DICHLOROBENZENE	1.0	--	--	--	--
CIS-1,2-DICHLOROETHYLENE	1.0	--	--	--	--
SURROGATE % RECOVERY					
4-BROMOFLUOROBENZENE		119.12%	80.81%		

TR = TRACE AMOUNT DETECTED

-- = NONE DETECTED

MDL = METHOD DETECTION LIMIT

ANALYST

W. S. 1, Sept 28/88

SAMPLE ID	AG MG/L	AL MG/L	B MG/L	BA MG/L	BE MG/L	CA MG/L	CD MG/L	CO MG/L	CR MG/L
SAMPLE 4-A	<.005	<.01	.103	.066	<.0005	115	<.01	<.05	<.01
CONTROL DATA	--	--	--	--	--	--	--	--	--
BLANK	<.005	<.01	<.004	<.005	<.0005	.04	<.01	<.05	<.01
SAMPLE 4-A	<.005	<.01	.103	.066	<.0005	115	<.01	<.05	<.01
SAMPLE 4-A-R	<.005	<.01	.107	.065	<.0005	114	<.01	<.05	<.01
CONTROL STD	.007	.95	.207	1.01	.0184	.10	.19	.17	.20
CONTROL EST.	--	1.00	.200	--	.0200	--	.20	.20	.20
EPA STD	.005	<.01	.107	<.005	<.0005	39.3	<.01	<.05	.01
EPA STD(CRT)	--	--	--	--	--	40.0	--	--	--

SAMPLE ID	CU MG/L	FE MG/L	K MG/L	MG MG/L	MN MG/L	MO MG/L	NA MG/L	NI MG/L	P MG/L
SAMPLE 4-A	<.008	.04	12.8	10.6	.05	<.2	3.6	<.05	<.5
CONTROL DATA	--	--	--	--	--	--	--	--	--
BLANK	<.008	<.01	<.5	<.01	<.01	<.2	<.5	<.05	<.5
SAMPLE 4-A	<.008	.04	12.8	10.6	.05	<.2	3.6	<.05	<.5
SAMPLE 4-A-R	<.008	.06	12.8	10.6	.05	<.2	3.6	.05	<.5
CONTROL STD	.195	.97	<.5	<.01	.19	<.2	<.5	.20	<.5
CONTROL EST.	.200	1.00	--	--	.20	--	--	.20	--
EPA STD	<.008	.05	9.9	10.3	<.01	<.2	40.8	<.05	<.5
EPA STD(CRT)	--	--	10.0	10.0	--	--	40.0	--	--

[illegible]